MONTGOMERY COUNTY

BRIDGE SCOUR MAINTENANCE PROJECT

Bridge 9 – CR 575 W over North Fork of Coal Creek
Bridge 14 – CR 700 E over Little Potato Creek
Bridge 25 – CR 700 E over Sugar Creek
Bridge 95 – CR 80 N over Black Creek
Bridge 127 – CR 400 S over Offield Creek
Bridge 134 – CR 100 E over Offield Creek
Bridge 136 – CR 200 E over Offield Creek
Bridge 174 – CR 550 E over Haw Creek

Bridge 197 – CR 1200 S over Big Racoon Creek



Jon Clodfester, PE

United Consulting 8440 Allison Pointe Blvd.

Suite 200

Indianapolis, IN 46250



John SanGiorgio, PE United Consulting

8440 Allison Pointe Blvd. Suite 200

Suite 200

Indianapolis, IN 46250

SPECIFICATIONS AND CONTRACT DOCUMENTS for the BRIDGE SCOUR MAINTENANCE PROJECT

in

MONTGOMERY COUNTY, INDIANA

July 2024

BOARD OF COUNTY COMMISSIONERS MONTGOMERY COUNTY

John E. Frey, Board President

Jim Fulwider, Board Vice President

Dan Guard, Member

AUDITOR: Mindy Byers

PREPARED BY:



United Consulting 8440 Allison Pointe Blvd. Suite 200 Indianapolis, IN 46250 Phone: (317) 895-2585

Fax: (317) 895-2596 Web: www.ucindy.com

Bridge Scour Maintenance Project

for Montgomery County Bridge No. 9, 14, 25, 95, 127, 134, 136, 174, 197

TABLE OF CONTENTS

SECTION	PAGES
PART I - BIDDING REQUIREMENTS	
Bridge Identification and Location	6
Notice to Bidders	7 - 8
Proposal	9 - 10
Contract Documents and Addenda	11
Exceptions	12
E-Verify Program	13
Itemized Proposal	14 - 17
PART II - CONTRACT FORMS	
Form No. 96	18 - 23
Bid Bond	24 - 25
Payment Bond	26 - 27
Performance Bond	28 - 29
Non-Collusion Affidavit	30
Legal Status of Bidder	31
Contractor's Application for Payment	32
Change Order	33
Affidavit and Waiver of Lien	34
Certification Letter	35
PART III - CONDITIONS OF THE CONTRACT	
Scope of Work	36 - 37
Bridge Location Map	38 - 46
Construction Schematics	47 - 73
General Provisions	74 - 82
Special Provisions	83 - 88
Permits	89 - 90
County Map	91 - 92
Inspection Reports	93 – 111

~ INDEX TO THE ~ GENERAL PROVISIONS

GP1.	CONTRACT DOCUMENTS	74
GP2.	OWNER	74
GP3.	ENGINEER	74
GP4.	CONTRACTOR	74
GP5.	ALTERNATIVES	74
<i>GP6</i> .	EXAMINATION OF THE PROJECT SITE	74 - 75
<i>GP7</i> .	CONTRACT QUESTIONS	75
GP8.	PUBLIC OPENING OF BIDS	75
<i>GP9</i> .	AWARD OF CONTRACT	75
<i>GP10</i> .	NOTICE TO PROCEED	75
<i>GP11</i> .	PRECONSTRUCTION CONFERENCE	75
<i>GP12</i> .	PROGRESS SCHEDULE	75
<i>GP13</i> .	SUPERVISION	76
<i>GP14</i> .	RESIDENT SUPERINTENDENT	76
<i>GP15</i> .	PROJECT STAFFING	76
<i>GP16</i> .	NOTIFICATION OF WORK SCHEDULE	76
<i>GP17</i> .	PROJECT RESPONSIBILITY	76
<i>GP18</i> .	STANDARDS OF QUALITY	76
<i>GP19</i> .	SANITATION	77
<i>GP20</i> .	WARRANTY OF WORK	77
<i>GP21</i> .	INSPECTION OF WORK	77
<i>GP22</i> .	CHANGES IN THE WORK	77 – 78
<i>GP23</i> .	DELETION OF WORK	78
<i>GP24</i> .	DELAY AND EXTENSION OF TIME	78
<i>GP25</i> .	HOLIDAYS THAT WORK IS NOT PERMITTED	<i>78</i> – <i>79</i>
<i>GP26</i> .	PERMITS	79
<i>GP27</i> .	UTILITIES	79
<i>GP28</i> .	NON-DISCRIMINATION	79
<i>GP29</i> .	INSURANCE	79 – 81
<i>GP30</i> .	ADDITIONAL INSURED	81
<i>GP31</i> .	PROOF OF INSURANCE	81
<i>GP31</i> .	PARTIAL PAYMENTS	81 – 82
GP32	FINAL PAYMENT	82

~ INDEX TO THE ~ SPECIAL PROVISIONS

CONTRACT TIME	83
UTILITY INFORMATION	83 - 84
DISPOSAL OF EXCESS MATERIAL	84
OPEN BURNING OF NATURAL GROWTH	84
TREE AND LAWN PROTECTION	85
EROSION CONTROL PLAN PAY ITEMS	85
DECREASED OR INCREASED QUANTITIES OF WORK	85
TRAFFIC MAINTENANCE	85
EXISTING CONDITIONS OF UTILITIES, ADDITIONAL	85 - 88
RIGHT-OF-WAY, AND ENCROACHMENTS	
STANDARD SPECIFICATION	88
MAINTAINING PEDESTRIAN ACCESSIBILITY DURING	88
CONSTRUCTION	
	UTILITY INFORMATION DISPOSAL OF EXCESS MATERIAL OPEN BURNING OF NATURAL GROWTH TREE AND LAWN PROTECTION EROSION CONTROL PLAN PAY ITEMS DECREASED OR INCREASED QUANTITIES OF WORK TRAFFIC MAINTENANCE EXISTING CONDITIONS OF UTILITIES, ADDITIONAL RIGHT-OF-WAY, AND ENCROACHMENTS STANDARD SPECIFICATION MAINTAINING PEDESTRIAN ACCESSIBILITY DURING

Bridge Identification and Location

Department ("Owner"): Montgomery County Highway Department

Project/Work: Bridge Scour Protection Maintenance

Bridge	Bridge Name	NBI	Location	Latitude	Longitude
Number		Number			
54-00009	CR 575W over North	5400006	1 mile E of CR	40.18553 N	-87.01311 W
	Fork of Coal Creek		900 N		
54-00014	CR 700E over Little	5400009	0.1 miles N of	40.16596 N	-86.77103 W
	Potato Creek		CR 85 N		
54-00025	CR 700E over Sugar	5400018	0.8 miles S of	40.12422 N	-86.77205 W
	Creek		CR 650 N		
54-00095	CR 80N over Black	5400077	0.11 miles E	40.05149 N	-86.95970 W
	Creek		of CR 300 W		
54-00127	CR 400S over	5400100	0.1 miles W of	39.98146 N	-86.90365 W
	Offield Creek		US 231		
54-00134	CR 100E over	5400104	0.3 miles N of	39.9717 N	-86.88449 W
	Offield Creek		CR 500 S		
54-00136	CR 200E over	5400105	0.5 miles S of	39.97501 N	-86.86568 W
	Offield Creek		CR 400 S		
54-00174	CR 550E over Haw	5400130	0.1 miles S of	39.87891 N	-86.79897 W
	Creek		CR 1100 S		
54-00197	CR 1200S over Big	5400199	0.1 miles E of	39.86555 N	-86.85960 W
	Raccoon Creek		CR 240 E		

See the attached County Bridge Map attached to this bid document for further location information.

NOTICE TO BIDDERS

Notice is hereby given that Montgomery County, by and through its Board of County Commissioners, will receive sealed bids for the construction of :

Bridge Scour Maintenance Project, Montgomery County Bridge No. 9, 14, 25, 95, 127, 134, 136, 174, 197

Sealed proposals will be received at the Montgomery County Auditor's Office, 1580 Constitution Row, Suite A, Crawfordsville, IN, 47933, until 4:00 p.m. on September 6, 2024. Bids received after the 4:00 p.m. deadline will not be considered but will be returned to the bidder unopened. All proposals will then be publicly opened and read aloud at the County Commissioner's Meeting at 8:00 a.m. on September 9, 2024.

The work to be performed and the proposals to be submitted shall include a bid for all general construction, labor, material, tools, equipment, taxes, permits, licenses, insurance, service costs, etc. incidental to and required for this project.

All materials furnished and labor performed incidental to and required by the proper and satisfactory execution of the contracts to be made, shall be furnished and performed in accordance with requirements from the drawings and specifications included in these documents. Copies of the Plans, Specifications, and bidding documents may be obtained in the Office of the Montgomery County Auditor, 1580 Constitution Row, Suite A, Crawfordsville, IN, 47933.

Each proposal must be enclosed in a sealed envelope with the supplied sealed bid notice, bearing the title of the project, bid opening date and the name and address of the bidder firmly attached. The proposal shall be accompanied by a certified check or acceptable *Bidder's Bond*, made payable to the Montgomery County Auditor, in a sum of not less than *five percent* of the total amount of the proposal, which check or bond will be held by the said Montgomery County as evidence that the bidder will, if awarded a contract, enter into the same with the *OWNER* upon notification from him to do so within ten days of said notification. Failure to execute the contract and to furnish performance bond to Montgomery County, will be cause for forfeiture of the amount of money represented by the certified check, or bidder's bond, as and for liquidated damages. Form 96, as prescribed by the Indiana State Board of Accounts, shall be properly completed, and submitted with bid proposals.

Proposals may be held by the Board of Commissioners for a period not to exceed sixty (60) days from the opening date.

The successful Contractor will be required to furnish a Performance Bond in the amount of one hundred percent (100%) of the Contract price within ten (10) days after award of contract.

No Contractor may withdraw his proposal within sixty (60) days after the opening date.

The Board of Commissioners reserves the right to reject any or all proposals, to waive technicalities or irregularities therein, to delete any item or items and to award a contract on the proposal that in their judgment is the most advantageous to Montgomery County.

BOARD OF COMMISSIONERS MONTGOMERY COUNTY, INDIANA

>NOTICE<

Sealed Bid Documents shall contain on the outside of the sealed envelope the following completed self-sticking label:

Equipment Type		
Annual Bid Category # Road Contract # / Bridge # (C (Circle One)	Desc.)	
Name of Bidder:		
Bid Opening Date:		
Other Documents Enclosed:		
Bid Bond Certified Check Form 95 Form 96 Other	(Y) (Y) (Y) (Y)	(N) (N) (N) (N)
For Montgomery County Received by the Montgo Commissioners File Stamp	omery Co.	

All mailer packets will be opened upon receipt. Make sure the sealed envelope is contained within.

>NOTICE<

PROPOSAL

To the Board of County Commissioners of Montgomery County, of the State of Indiana; hereinafter referred to as *OWNER*:

Bridge Scour Maintenance Project Montgomery County Bridge No. 9, 14, 25, 95, 127, 134, 136, 174, 197

Pursuant to the legal notice that sealed proposals for the above project would be received by the Board of County Commissioners of Montgomery County,

The undersigned hereby tenders this bid to construct the work in accordance with the plans, profiles, drawings, specifications, and all authorized revisions for this contract which are on file in the office of the Montgomery County Highway Department; and to furnish all necessary machinery, equipment, tools, labor and other means of construction and to furnish all material specified in the manner and at the time prescribed and under the supervision and direction of the *OWNER* or his duly authorized representative and pursuant to the terms of the *Performance Bond* and the *Payment Bond* in the amounts of not less than *One Hundred Percent* of the amount of the Proposal, for the unit prices given on the attached Itemized Proposal dated ______

Together with this PROPOSAL, the undersigned has:

- A. Filed an Itemized Proposal with a unit price and extension for each item listed, together with a total amount for all items, based upon the unique characteristics of this contract;
- B. Executed the Form No. 96 filed herewith;
- C. Filed a properly executed Bid Bond or certified check made payable to the Montgomery County Highway Department herewith in an amount greater than or equal to ten percent of the amount of this proposal;
- D. Executed the Non-Collusion affidavit filed herewith
- E. Executed the Legal Status of Bidder Form filed herewith;
- F. Filed a current Financial Statement herewith;

If awarded the contract, the undersigned promises to prosecute the work so as to complete the contract within the time specified in the Special Provisions.

Witness our	hands this	day of	
Firm Name			
Address			
	By:		
		(Signature)	
	Name:		
		(Printed)	
	Title:		
		(Printed)	

CONTRACT DOCUMENTS AND ADDENDA

The Bidder agrees to be bound by the terms and provisions of all Contract Documents as define
in the General Conditions and incorporates such Contract Documents herein by reference
The Bidder acknowledges receipt of the following addenda:

Addendum Number	Date

EXCEPTIONS

Instructions To Bi	dders:	
The Bidder shall f	ully state each exception taken to the Specifications or other Con	tract
Documents in thi	s Part.	
Bidder is cautione	ed that any exception taken by Bidder and deemed by Owner to be	e a material
qualification or va	ariance from the terms of the Contract Documents may result in t	his Bid being
rejected as non-re	esponsive.	
Exceptions:		
-		_

E-VERIFY PROGRAM

Pursuant to Indiana Code 22-5-1.7-11, the contractor awarded the Bid is required to enroll in and verify the work eligibility status of all its newly hired employees through the E-Verify program. The contractor who is awarded the Bid is not required to verify the work eligibility status of all its newly hired employees through the E-Verify program if the E-Verify program no longer exists.

The individual person(s) executing this Proposal, being first duly sworn, depose(s) and state(s) that the Bidder does not knowingly employ an unauthorized alien. The undersigned further affirms that, prior to entering into an agreement for this Bid, the undersigned business entity will enroll in and agrees to verify the work eligibility status of all its newly hired employees through the E-Verify program.

Itemized Proposal

Montgomery County Bridge No. 9, 14, 25, 95, 127, 134, 136, 174, 197
Bridge Scour Maintenance
Summary of Bid

:	*Base Bid:
:	*Alternative Bid 1:
:	*Alternative Bid 2:
:	*Alternative Bid 3:
:	*Alternative Bid 4:
:	*Alternative Bid 5:
:	*Alternative Bid 6:
:	*Alternative Bid 7:
:	*Alternative Bid 8:
:	*Total of Base Bid plus All Alternative Bids:
	Submitted By:
	Signature:
	Title:
:	Address:

*Note: Bid amounts listed above will be read aloud at the time of bid opening and used for announcing the apparent low bidder. Therefore, it the bidder's responsibility to ensure the amounts listed match those included in the Itimized proposal. Neither the Owner nor the Engineer shall be required to discover or correct any error or omission and the Bidder shall assume the risk of and be bound to the consequences of any such error or omission.

**Note: This amount to shall be used to calculate Bid Security and the amounts listed in the Bidders Itemized Proposal and Declarations.

ITEMIZED PROPOSAL

MONTGOMERY COUNTY BRIDGE SCOUR MAINTENANCE July, 2024

ITEM No.	INDOT ITEM	DESCRIPTION	TOTAL QUANTITY	UNIT	UNIT PRICE	EXTENSION
		Bridge 9 Pa	ny Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	376	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	319	SYS		
					SUBTOTAL:	
		Bridge 14 P	ay Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	246	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	190	SYS		
					SUBTOTAL:	
		Bridge 25 P	av Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	528	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	437	SYS		
			·		SUBTOTAL:	
		Bridge 95 P	av Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	299	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	233	SYS		
		•			SUBTOTAL:	

ITEMIZED PROPOSAL

MONTGOMERY COUNTY BRIDGE SCOUR MAINTENANCE July, 2024

ITEM No.	INDOT ITEM	DESCRIPTION	TOTAL QUANTITY	UNIT	UNIT PRICE	EXTENSION
		Bridge 12	7 Pay Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	222	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	169	SYS		
					SUBTOTAL:	
		Bridge 13	4 Pay Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	236	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	235	SYS		
II.					SUBTOTAL:	
		Bridge 13	6 Pay Items			
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	264	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	207	SYS		
	010 122 10	000.00.000.0000.0000.0000.0000.0000.0000	20.		SUBTOTAL:	
		D.11. 17	4 D			
1 1	110-01001		4 Pay Items	1.0		
1		MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	616-05688	RIPRAP CLASS 1	323	TON		
5	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	263	SYS	<u> </u>	
					SUBTOTAL:	

ITEMIZED PROPOSAL

MONTGOMERY COUNTY BRIDGE SCOUR MAINTENANCE July, 2024

ITEM No.	INDOT ITEM	DESCRIPTION	TOTAL QUANTITY	UNIT	UNIT PRICE	EXTENSION
	Bridge 197 Pay Items					
1	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS		
2	206-51235	STORMWATER MANAGEMENT BUDGET	1	LS		
3	206-51235	COFFERDAM	1	LS		
4	301-12231	COMPACTED AGGREGATE NO. 2	9	CYS		
5	301-12234	COMPACTED AGGREGATE NO. 53	9	CYS		
6	616-05688	RIPRAP CLASS 1	352	TON		
7	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	297	SYS		
SUBTOTAL:					SUBTOTAL:	
					<u></u>	
					TOTAL:	

PART I (To be completed for all bids. Please type or print)

		Date (month, day, year):
	1.	Governmental Unit (Owner):
	2.	County:
	3.	Bidder (Firm):
		Address:
		City/State/ZIPcode:
	4.	Telephone Number:
	5.	Agent of Bidder (if applicable):
	Pι	rsuant to notices given, the undersigned offers to furnish labor and/or material necessary to complete
the pub	lic '	works project of
(Goverr	nme	ental Unit) in accordance with plans and specifications prepared by
		and dated for the sum of
		\$

The undersigned further agrees to furnish a bond or certified check with this bid for an amount specified in the notice of the letting. If alternative bids apply, the undersigned submits a proposal for each in accordance with the notice. Any addendums attached will be specifically referenced at the applicable page.

If additional units of material included in the contract are needed, the cost of units must be the same as that shown in the original contract if accepted by the governmental unit. If the bid is to be awarded on a unit basis, the itemization of the units shall be shown on a separate attachment.

The contractor and his subcontractors, if any, shall not discriminate against or intimidate any employee, or applicant for employment, to be employed in the performance of this contract, with respect to any matter directly or indirectly related to employment because of race, religion, color, sex, national origin or ancestry. Breach of this covenant may be regarded as a material breach of the contract.

CERTIFICATION OF USE OF UNITED STATES STEEL PRODUCTS (If applicable)

I, the undersigned bidder or agent as a contractor on a public works project, understand my statutory obligation to use steel products made in the United States (I.C. 5-16-8-2). I hereby certify that I and all subcontractors employed by me for this project will use U.S. steel products on this project if awarded. I understand that violations hereunder may result in forfeiture of contractual payments.

ACCEPTANCE

	The above bid is acc	cepted this	day o	of		subject to the
followi	ng conditions:					
Contra	acting Authority Membe	ers:				
	(1	For projects of \$1	PART II Í 0.000 or ma	ore – IC	36-1-12-4)	
	,	, , , , , , , , , , , , , , , , , , ,			,	
	Governmenta	al Unit:				
	Bidder (Firm)					
	Date (month,	day, year):				
Attach	These statements to additional pages for e			n bidder v	with and as a part of his bid	d.
Attaon	additional pages for e	SECTION I EX		OHEST		
4	\\/\bat mublic weeks m					
1.	date of the current b		gariization con	ipietea ic	or the period of one (1) yea	al prior to trie
	Contract Amount	Class of Work		oletion ate	Name and Address of	of Owner
2.	What public works p	rojects are now in p	process of con	struction	by your organization?	
	Contract Amount	Class of Work	Comp	ected pletion ate	Name and Address of	of Owner

3.	Have you ever failed to complete any work awarded to you?	If so, where and why?
ŀ.	List references from private firms for which you have performed work.	
	SECTION II PLAN AND EQUIPMENT QUESTIONNAI	RE
	Explain your plan or layout for performing proposed work. (Examples could in you could begin work, complete the project, number of workers, etc. and any believe would enable the governmental unit to consider your bid.)	
	Please list the names and addresses of all subcontractors (i.e. persons or firr who have performed part of the work) that you have used on public works proyears along with a brief description of the work done by each subcontractor.	

If you intend to sublet any portion of the work, state the name and address of each subcontractor, equipment to be used by the subcontractor, and whether you will require a bond. However, if you are unable to currently provide a listing, please understand a listing must be provided prior to contract approval. Until the completion of the proposed project, you are under a continuing obligation to immediately notify the governmental unit in the event that you subsequently determine that you will use a subcontractor on the proposed project.
What equipment do you have available to use for the proposed project? Any equipment to be used by subcontractors may also be required to be listed by the governmental unit.
Have you entered into contracts or received offers for all materials which substantiate the prices used in preparing your proposal? If not, please explain the rationale used which would corroborate the prices listed.

SECTION III CONTRACTOR'S FINANCIAL STATEMENT

Attachment of bidder's financial statement is mandatory. Any bid submitted without said financial statement as required by statute shall thereby be rendered invalid. The financial statement provided hereunder to the governing body awarding the contract must be specific enough in detail so that said governing body can make a proper determination of the bidder's capability for completing the project if awarded.

SECTION IV CONTRACTOR'S NON - COLLUSION AFFIDAVIT

The undersigned bidder or agent, being duly sworn on oath, says that he has not, nor has any other member, representative, or agent of the firm, company, corporation or partnership represented by him, entered into any combination, collusion or agreement with any person relative to the price to be bid by anyone at such letting nor to prevent any person from bidding nor to include anyone to refrain from bidding, and that this bid is made without reference to any other bid and without any agreement, understanding or combination with any other person in reference to such bidding.

He further says that no person or persons, firms, or corporation has, have or will receive directly or indirectly, any rebate, fee, gift, commission or thing of value on account of such sale.

SECTION V OATH AND AFFIRMATION

Dated at		this	day of	,
			(Name of Organization)	
	Ву			
			(Title of Person Signing)	· · · · · · · · · · · · · · · · · · ·
			(Title of Person Signing)	
	ACKN	OWLEDGEM	ENT	
STATE OF)			
COUNTY OF) ss)			
	·············/			
Before me, a Notary Public, person	ally appeared th	e above-name	d	and
swore that the statements contained	d in the foregoin	g document ar	e true and correct.	
Subscribed and sworn to before me	this	day of		
			Notary Public	

My Commission Expires:

County of Residence:

BID OF
(Contractor
(Address
FOR
PUBLIC WORKS PROJECTS
OF

Filed,
Action taken

BID BOND

KNOWN BY ALL PERSONS BY THESE PRESENTS THAT THE UNDERSIGNED:

BIDDER:	
as principal, and	
SURETY: [Name]	
[Address]	

as Surety,

are firmly bound unto the Board of County Commissioners of Montgomery County, Indiana in the full and just sum of an amount equal to *FIVE PERCENT* of the amount of the Principal's bid, to the payment of which, well and truly to be made, we bind ourselves jointly and severally, and our joint and several heirs, executors, administrators and assigns, firmly by these presents.

THE CONDITIONS OF THE ABOVE OBLIGATIONS ARE SUCH THAT, whereas, the Principal is herewith submitting a bid and proposal for construction and completion of this contract in accordance with plans and specifications, which are made part of this bond;

NOW, THEREFORE, if the Board of County Commissioners of Montgomery County shall award the Principal the contract and the Principal shall promptly enter into a contract with the Board of County Commissioners of Montgomery County, then this obligation shall be void; otherwise to remain in full force, virtue, and effect.

IT IS AGREED that no modifications, omissions, or additions in or to the terms of such contract or in or to the plans or specifications therefore shall affect the obligation of such sureties on this bond.

IN WITNESS WHEREOF, we hereto set our hands and seals:

<< *BIDDER* >>

(Bid Bond)	
	(Signature)
	(Printed)
	(Title)
State of Indiana. County of	, SS:
a hond on this day of	as Principal and acknowledged the execution of the above,
My Commission Expires:	
(County of Residence)	(Notary Signature & Seal)
	<< SURETY >>
(Bid Bond)	
	(Signature)
	(Printed)
	(Title)
State of Indiana. County of	, SS:
above bond on this day of	as Surety and acknowledged the execution of the,
My Commission Expires:	

PAYMENT BOND

KNOWN BY ALL PERSONS BY THESE PRESENTS THAT THE UNDERSIGNED:

CONTRACTOR:		
as principal, and		
SURETY: [Name]		
[Address]		

as Surety,

are firmly bound unto the Board of County Commissioners of Montgomery County, Indiana in the penal sum of an amount equal to *ONE HUNDRED PERCENT* of the amount of the Principal's bid, if the proposal is accepted, for the payment of which, well and truly made, we bind ourselves jointly and severally, and our joint and several heirs, executors, administrators and assigns, firmly by these presents.

THE CONDITIONS OF THE ABOVE OBLIGATION ARE SUCH THAT, whereas, the Principal is herewith submitting a bid and proposal for construction and completion of this contract in accordance with plans and specifications, which are made part of this bond;

NOW, THEREFORE, if the Board of County Commissioners of Montgomery County shall award the Principal the contract for work and the Principal shall promptly enter into a contract with the Board of County Commissioners of Montgomery County, for the work and shall promptly make payments of all amounts due to all Claimants, then this obligation shall be void; otherwise to remain in full force, virtue, and effect. Claimant shall mean any subcontractor, material supplier or other person, firm, or corporation furnishing materials or equipment for or performing labor or services in the prosecution of the work provided in such an agreement, including lubricants, oil, gasoline, coal, and coke, repairs on machinery, and tools, whether consumed or used in connection with the construction of such work, and all insurance premiums on said work, and for all labor, performed in such work.

IT IS AGREED that no modifications, omissions, or additions in or to the terms of such contract or in or to the plans or specifications therefore shall affect the obligation of such sureties on this bond.

IN WITNESS WHEREOF, we hereto set our hands and seals:

<< CONTRACTOR >>

(Payment Bond)					
	(Signature)				
	(Printed)				
	(Title)				
State of Indiana. County of	otary Public, personally appeared;				
above bond on this	as Principal and acknowledged the execution of the day of,				
My Commission Expires:					
(County of Residence)	(Notary Signature & Seal)				
(Payment Bond)	<< SURETY >>				
	(Signature)				
	(Printed)				
	(Title)				
State of Indiana. County of	otary Public, personally appeared;				
above bond on this	as Surety and acknowledged the execution of the day of,				
My Commission Expires:					
(County of Residence)	(Notary Signature & Seal)				

PERFORMANCE BOND

KNOWN BY ALL PERSONS BY THESE PRESENTS THAT THE UNDERSIGNED:

CONTRACTOR:	
as principal, and	
SURETY: [Name]	
[Address]	

as Surety,

are firmly bound unto the Board of County Commissioners of Montgomery County, Indiana in the penal sum of an amount equal to *ONE HUNDRED PERCENT* of the amount of the Principal's bid, if the proposal is accepted, for the payment of which, well and truly made, we bind ourselves jointly and severally, and our joint and several heirs, executors, administrators and assigns, firmly by these presents.

THE CONDITIONS OF THE ABOVE OBLIGATION ARE SUCH THAT, whereas, the Principal is herewith submitting a bid and proposal for construction and completion of this contract in accordance with plans and specifications, which are made part of this bond;

NOW, THEREFORE, if the Board of County Commissioners of Montgomery County shall award the Principal the contract for work and the Principal shall promptly enter into a contract with the Board of County Commissioners of Montgomery County, for the work and shall well and faithfully do and perform the same in all respects according to the plans and specifications and according to the time, terms, and conditions specified in this contract to be entered into, and in accordance with all requirements of law and shall promptly pay all debts incurred by the Principal or a subcontractor in the construction of the work, including labor, service, and materials furnished, and shall remain in effect at least until one year after the date when final payment becomes due, then this obligation shall be void; otherwise to remain in full force, virtue, and effect.

IT IS AGREED that no modifications, omissions, or additions in or to the terms of such contract or in or to the plans or specifications therefore shall affect the obligation of such sureties on this bond.

IN WITNESS WHEREOF, we hereto set our hands and seals:

<< CONTRACTOR >>

(Performance Bond)						
	(Signature)					
	(Printed)					
	(Title)					
State of Indiana. County of	Notary Public, personally appeared;					
	as Principal and acknowledged the execution of the					
above bond on this day	as Principal and acknowledged the execution of the of,					
My Commission Expires:						
(County of Residence)	(Notary Signature & Seal)					
	<< SURETY >>					
(Performance Bond)						
	(Signature)					
	(Printed)					
	(Title)					
State of Indiana. County of	y Public, personally appeared;					
above bond on this day	as Surety and acknowledged the execution of the of					
My Commission Expires:						
(County of Residence)	(Notary Signature & Seal)					

NON-COLLUSION AFFIDAVIT

STATE OF	.)
COUNTY OF)) SS
other member, representative, or agent of represented by it, entered into any combination to the price to be bid by anyone, nor to preven refrain from bidding, and that this bid is made	y sworn, on oath, says that it has not, nor has any the firm, company, corporation or partnership on, collusion or agreement with any person relative at any person from bidding nor to induce anyone to without reference to any other bid and without any th any other person in reference to such bidding in
BY	(Signature)
	(Title)
FOR	
	(Firm or Corporation)
Before me, the undersigned as Notary Public	, personally appeared;
this	,,,
My Commission Expires:	
(County of Residence)	(Notary Signature & Seal)

LEGAL STATUS OF BIDDER

This Proposar is submitted in the	name or:		
Firm Name			
The undersigned hereby design communications may be served of		ness address to which all notices, di	irections or other
Street			
City			
State		Zip Code	
The undersigned hereby declares	that he has legal stat	us checked below:	
CO-PARTNERSHIP County of CORPORATION INC The Cor	(The Assumed name, Ind:, Ind:, CORPORATED UNI poration is: LICENSED TO DO I	ER AN ASSUMED NAME of the partnership is registered in the iana. DER THE LAWS OF THE STATE OF BUSINESS IN INDIANA ED TO DO BUSINESS IN INDIANA	
	•	are officers or Partners in the organization	ion are as follows:
NAME AND TITLE		HOME ADDRESS	
	-		
Signed and Sealed this	day of		
	Ву	(Signature)	
		(Printed)	
		(Title)	

Montgomery County Highway Department 1580 Constitution Row Crawfordsville, IN 47933]	PROGRESS ESTIM PARTIAL FINA	PROJECT:		
EM NO.	ITEM DESCRIPTION	UNITS	UNIT PRICE	PLAN QUANTITY	QNTY THIS ESTIMATE	QNTY TO DATE	EXTENSION
				~	~	~	
CONTRACTOR: BY: APPROVED BY: APPROVED BY:		DATI DATI DATI		LESS RETA: PREVIOUS I	RNINGS TO DATE: INED PERCENTAGI PAYMENTS: UE CONTRACTOR:		

MONTGOMERY COUNTY HIGHWAY DEPARTMENT

CHANGE ORDER

Project I	No. Description:				Contr	act No.				
Whereas	=	pecifications for the on and reason)	nis contr	act provides f	for such work	to be performe	ed, the following	ng change is	recomme	nded.
ITEM DESCRIPTION OF ITEM					INCREASE		DECREASE		% CHANGE	
			UNIT PRICE	QUANTITY	AMOUNT	QUANTITY	AMOUNT	THIS C.O.	TO DATE	
	PLACE "EW" FOR EXTRA WORK ITEMS		EMS	TO						
	PLACE "FA" FOR FORCE ACCOUNT ITEMS			NCREASED ESTIMATED COST \$						
has been intent o	n moved to f the parties tha	extended / reduce t this change orc nge in plans is h	ler is fu	to acco	ommodate the lete compens	e changes ma	ade in this cha	ange order.	It is the	
Contrac	tor:				By: Citle:			Date:		
	omitted for nsideration									
P.1		onst. ingr.								
Cou Eng	•	Dir. ligh.								
				Approve	d for Montg	omery Coui	nty Highway	Departmen	ıt	
(Sign	nature)		_	(T	itle)			— (Da	.te)	

AFFIDAVIT AND WAIVER OF LIEN

	☐ Final ☐ Partia	al Payment to Follow		
State of Indiana, County of	SS			
(Name of Officer)	being duly sworn states	that he is the		of
(Subcontractor/Supplier)	having contrac	ted with(CONTRACTOR)	t	o furnish certain
materials and/or labor as follows	\$			
for the project known as	Montgomery Count	y Bridge Scour Mainter	nance Project	
located atand does hereby further state on	and owned by behalf of the aforemention	the Board of Coun ed subcontractor/supplier	ity Commissior :	ners of Montgomery Count
(PARTIAL WAIVER) that there is	due from the <i>CONTRACTOF</i>	?the sum of		
		_	Dollars(\$)
 receipt of which is heret the payment of which he given solely with respect to see the undersigned: (FINAL WAIVER) that the final bases	as been promised as the sol aid amount and which waive	er shall be effective only u	idavit and Parti pon receipt of	al Waiver of Lien which is payment thereof by
			Dollars(\$)
() receipt of which is herek () the payment of which ha become effective upon i	as been promised as the sole	e consideration for this Aff	idavit and Final	Waiver of Lien which shall
THEREFORE, the undersigned wa above-described property and in thereto, subject to limitations or of to a lien on account of any work paffidavit and waiver.	nprovements thereon on acconditions expressed herein	count of LABOR or mater , if any; and further certifie	ial or both, furi s that no other	nished by the undersigned party has any claim or right
(Firm)	_ By	Title		
(FITTII)	(Authorizea Repré	esemalive)		
WITNESS MY HAND AND NOTA	RIAL SEAL this d	ay of20		
		(Notary Public)	1	
My Commission Expires	F	Printed		
Residing in	County			

CERTIFICATION LETTER

TO BE COMPLETED BY ALL SUB-CONTRACTORS AND MATERIAL SUPPLIERS

Reference:

Bridge Scour Maintenance Project **Montgomery County**

We hereby certify that we have examined the Contract Plans and Specifications for this project and that all materials and workmanship will be in strict compliance therewith.

Company Name	-		
Address			
<u>—</u> Ву			
Ву		(Signature)	
		(Dwinted)	
		(Printed)	
		(Title)	
Date			
Describe Item of work or	material to be fu	ırnished:	
	Copy to:	United Consulting 8440 Allison Pointe Blvd. Suite 200	

Indianapolis, Indiana, 46250

Scope of Work

BRIDGE 9:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope and around each cone of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 14:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 25:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 95:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 127:

- Place temporary cofferdams under the bridge for pier riprap installation. Only one cofferdam may be placed at a time in order to not restrict channel flow.
- Install 36" Class I Riprap 6' in each direction on unprotected perimeter around piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 134:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 136:

- Place temporary cofferdams under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 174:


- Place temporary cofferdam under the bridge for pier riprap installation.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.

BRIDGE 197:

- Place temporary cofferdams under the bridge for pier riprap installation. Only one cofferdam may be placed at a time in order to not restrict channel flow.
- Install 24" Class I Riprap along the existing spillslopes. Riprap is to extend from the toe of the slope to the top of the slope.
- Install 36" Class I Riprap 6' in each direction around the piers.
- All new riprap is to be placed on Geotexiles for Riprap Type 1A.
- Place a 3' wide compacted aggregate animal crossing as shown on the elevation sheet.


Montgomery County Bridge 9 Location

CR 575 W over North Fork of Coal Creek 1.0 Miles E of CR 900 N



Montgomery County Bridge 14 Location

CR 700 E over Little Potato Creek 0.1 Miles N of CR 85



Montgomery County Bridge 25 Location

CR 700 E over Sugar Creek 0.8 Miles S of CR 650 N



Montgomery County Bridge 95 Location

CR 80 N over Black Creek 0.1 Miles E of CR 300 W




Montgomery County Bridge 127 Location

CR 400 S over Offield Creek 0.1 Miles W of US 231




Montgomery County Bridge 134 Location

CR 100 E over Offield Creek 0.3 Miles N of CR 500 S



Montgomery County Bridge 136 Location

CR 200 E over Offield Creek 0.5 Miles S of CR 400 S



Montgomery County Bridge 174 Location

CR 550 E over Haw Creek 0.1 Miles S of CR 1100 S




Montgomery County Bridge 197 Location

CR 1200 S over Big Raccoon Creek 0.1 Miles E of CR 240 E







CR 575 W OVER NORTH FORK OF COAL CREEK




MONTGOMERY COUNTY BRIDGE No. 9 CR 575 W OVER NORTH FORK OF COAL CREEK






MONTGOMERY COUNTY BRIDGE No. 9 CR 575 W OVER NORTH FORK OF COAL CREEK

EROSION CONTROL PLAN




50

MONTGOMERY COUNTY HIGHWAY DEPARTMENT CR 700 E OVER LITTLE POTATO CREEK



MONTGOMERY COUNTY BRIDGE No. 14 CR 700 E OVER LITTLE POTATO CREEK




MONTGOMERY COUNTY BRIDGE No. 14 CR 700 E OVER LITTLE POTATO CREEK

EROSION CONTROL PLAN




MONTGOMERY COUNTY BRIDGE No. 25 CR 700 E OVER SUGAR CREEK



NOTE: Vertical Datum is NAVD88


MONTGOMERY COUNTY HIGHWAY DEPARTMENT MONTGOMERY COUNTY BRIDGE No. 25 CR 700 E OVER SUGAR CREEK




MONTGOMERY COUNTY BRIDGE No. 25 CR 700 E OVER SUGAR CREEK




CR 80 N OVER BLACK CREEK



MONTGOMERY COUNTY BRIDGE No. 95 CR 80 N OVER BLACK CREEK




MONTGOMERY COUNTY BRIDGE No. 95 CR 80 N OVER BLACK CREEK




HIGHWAY DEPARTMENT

CR 400 S OVER OFFIELD CREEK




MONTGOMERY COUNTY BRIDGE No. 127 CR 400 S OVER OFFIELD CREEK




61

MONTGOMERY COUNTY HIGHWAY DEPARTMENT MONTGOMERY COUNTY BRIDGE No. 127 CR 400 S OVER OFFIELD CREEK


EROSION CONTROL PLAN



HIGHWAY DEPARTMENT




MONTGOMERY COUNTY BRIDGE No. 134 CR 100 E OVER OFFIELD CREEK




MONTGOMERY COUNTY BRIDGE No. 134 CR 100 E OVER OFFIELD CREEK






MONTGOMERY COUNTY BRIDGE No. 136 CR 200 E OVER OFFIELD CREEK



NOTE: Contractor is responsible for permitting any tree cleaning to install the riprap and access causeways.




MONTGOMERY COUNTY HIGHWAY DEPARTMENT MONTGOMERY COUNTY BRIDGE No. 136 CR 200 E OVER OFFIELD CREEK

EROSION CONTROL PLAN



68

HIGHWAY DEPARTMENT




LEGEND:



Riprap, Class I


MONTGOMERY COUNTY HIGHWAY DEPARTMENT MONTGOMERY COUNTY BRIDGE No. 174 CR 550 E OVER HAW CREEK




70

MONTGOMERY COUNTY HIGHWAY DEPARTMENT CR 550 E OVER HAW CREEK

EROSION CONTROL PLAN




HIGHWAY DEPARTMENT



NOTE: Vertical Datum is NAVD88 Scale: 1:16

MONTGOMERY COUNTY HIGHWAY DEPARTMENT MONTGOMERY COUNTY BRIDGE No. 197 CR 1200 S OVER BIG RACCOON CREEK



MONTGOMERY COUNTY HIGHWAY DEPARTMENT

MONTGOMERY COUNTY BRIDGE No. 197 CR 1200 S OVER BIG RACCOON CREEK

GENERAL PROVISIONS

GP1. CONTRACT DOCUMENTS

The Indiana Department of Transportation, Standard Specifications dated 2024 shall be used in conjunction with these Plans, Contract Forms, General Provisions, Special Provisions, Modifications to the Specifications, Standard Sheets and any addenda which may be issued for this project.

It is the intent of these Contract Documents to describe a functionally complete project to be constructed in accordance therewith. Any work, materials or equipment that may reasonably be inferred will be supplied whether or not specifically called for.

Wherever reference is made to the Indiana Department of Transportation, Director, or Chief Highway Engineer, it shall be interpreted as the Board of County Commissioners of Montgomery County, Indiana.

GP2. OWNER

The Board of County Commissioners of Montgomery County, Indiana.

GP3. ENGINEER

The Montgomery County Highway Engineer or its authorized representative.

GP4. CONTRACTOR

The Firm or Corporation with whom the *OWNER* has entered into the Construction Contract.

GP5. <u>ALTERNATIVES</u>

No alternatives will be considered unless they are specifically requested in writing by the *OWNER*.

GP6. EXAMINATION OF THE PROJECT SITE

Before the bid date, all bidders shall carefully and thoroughly examine the entire site of the proposed work and adjacent premises and the various means of approach and access thereto by means of a site inspection visit, and make all necessary investigations to inform themselves thoroughly as to the facilities necessary for delivering, placing, and operating the necessary construction equipment, and for delivering and handling materials at the site(s), and shall inform themselves thoroughly as to any and all actual or potential difficulties, hindrances, delays, and constraints involved in the commencement, prosecution and completion of the proposed work in accordance with the requirements of this contract. The *CONTRACTOR*, by the execution of the Contract, shall in no way be relieved of any obligation under it, due to his failure to receive or examine any form or legal instrument, are to visit the site(s) and acquaint himself with the

conditions there existing. The *OWNER* will be justified in rejecting any claim based on facts which he should have noticed as a result thereof.

GP7. CONTRACT QUESTIONS

Submit all questions in writing to *UNITED CONSULTING* prior to 4:00 p.m. local time, September 6, 2024. No questions will be answered by telephone. Questions shall be submitted via email (john.sangiorgio@ucindy.com).

GP8. PUBLIC OPENING OF BIDS

Bids will be opened publicly and read aloud at 8:00 a.m. local time, September 9, 2024, at the Montgomery County Commissioner's Meeting. Bidders, or their authorized agents, are invited to be present. Any Bids received after 8:00 a.m. local time, September 9, 2024, will be returned to the bidder unopened.

GP9. AWARD OF CONTRACT

The *OWNER* reserves the right to reject any or all bids or to waive any informalities and to accept the bid which it deems most favorable to the interest of the *OWNER* after all bids have been examined and scrutinized.

GP10. NOTICE TO PROCEED

The *CONTRACTOR* shall start to perform the work on the date designated in the written Notice to Proceed.

GP11. PRECONSTRUCTION CONFERENCE

Before the *CONTRACTOR* is issued a Notice to Proceed, a conference attended by the *OWNER*, *ENGINEER*, *CONTRACTOR* and others as appropriate will be held. The purpose of this conference will be to discuss procedures for making submittals, processing applications for payment, and to establish other procedures and understandings bearing upon coordination and performance of the work.

GP12. PROGRESS SCHEDULE

Within ten days after the date of the Notice to Proceed, the *CONTRACTOR* shall submit to the *ENGINEER* for review a proposed schedule indicating the starting and completion dates of the various stages of the work to be performed under this contract. The *ENGINEER* shall review the proposed schedule to determine conformity with the contract and will make recommendations to the *OWNER* concerning approval thereof; however the review, approval or other action taken by the *ENGINEER* or *OWNER* in respect of such schedules shall not relieve the *CONTRACTOR* of its obligations to perform the work within the contract schedule. *CONTRACTOR shall have a monthly progress meeting with the OWNER*.

GP13. SUPERVISION

The *CONTRACTOR* shall supervise and direct the work completely and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the work in accordance with the Contract Documents.

GP14. RESIDENT SUPERINTENDENT

The CONTRACTOR shall keep on the work site at all times during its progress, a competent resident superintendent, who shall not be replaced without written notice to the ENGINEER except under extraordinary circumstances. The superintendent will be the CONTRACTOR'S representative at the site and shall have authority to act on behalf of the CONTRACTOR. All communications given to the superintendent shall be as binding as if given to the CONTRACTOR.

GP15. PROJECT STAFFING

The *CONTRACTOR* shall provide competent, suitably qualified personnel to survey and lay out the work and perform construction as required by the Contract Documents. The *CONTRACTOR* shall at all times maintain good discipline and order at the site(s).

GP16. NOTIFICATION OF WORK SCHEDULE

The *CONTRACTOR* shall provide a listing of the next work day's work activities by 12:00 p.m. of that day's work for the *ENGINEER'S* scheduling and inspection. All work scheduled for Monday shall be provided on Friday of the preceding week.

Failure to provide such notice within the specified time may result in non-acceptance for any material placed that day.

GP17. PROJECT RESPONSIBILITY

Unless otherwise specified in the Contract Documents, the *CONTRACTOR* shall furnish and assume full responsibility for all materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, and sanitary facilities and all other facilities and incidentals necessary for the furnishing, performance, start-up, and completion of the work.

GP18. STANDARDS OF QUALITY

All materials and equipment shall be of good quality and new, except as otherwise provided in the Contract Documents. All warranties and guarantees specifically called for in the Contract Documents shall expressly run for the benefit of the *OWNER*. If requested by the *ENGINEER*, the *CONTRACTOR* shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

GP19. <u>SANITATION</u>

The *CONTRACTOR* shall introduce and enforce among this employees such regulations in regard to cleanliness and the disposal of garbage and waste shall comply with local ordinances. The *CONTRACTOR* shall take such means as the *OWNER* may direct to effectually prevent the creation of a nuisance on the work or any part of the property of the *OWNER*. The *CONTRACTOR* shall construct toilets and maintain them in sanitary condition, properly secluded from public observation, at such points as shall be approved. Under no circumstances shall the *CONTRACTOR* create or maintain a nuisance.

GP20. WARRANTY OF WORK

The *CONTRACTOR* warrants and guarantees to the *OWNER* that all work will be performed, supplied, furnished and installed, and that the work will perform in strict accordance with the Contract Documents and will not be defective. Notice of all work determined or suspected to be defective or not in conformity with the Contract Documents shall be given to the *CONTRACTOR* within reasonable time after observance thereof.

GP21. <u>INSPECTION OF WORK</u>

The *ENGINEER* and his representatives shall at all times have access to the work wherever it is in preparation or progress and the *CONTRACTOR* shall provide proper facilities for such access and for inspection.

If the specifications, the *ENGINEER*'s instructions, laws, ordinances or any public authority require any work to be specially tested or approved, the *CONTRACTOR* shall give the *ENGINEER* timely notice of its readiness for inspection and, if the inspection is by an authority other than the *ENGINEER*, the date fixed for such inspection. If any work should be covered up without the approval or consent of the *ENGINEER*, it must, if required by the *ENGINEER*, be uncovered for examination at the *CONTRACTOR'S* expense.

Re-examination of questioned work may be ordered by the *ENGINEER* and if so ordered the work must be uncovered by the *CONTRACTOR*. If such work is found to be in accordance with the Contract Documents, the *OWNER* shall pay the cost of the re-examination and replacement. If such work is not found to be in accordance with the Contract Documents, the *CONTRACTOR* shall pay the cost.

GP22. CHANGES IN THE WORK

The *OWNER*, without invalidating the Contract, may order extra work or make changes by altering, adding to or deducting from the work, the Contract Sum being adjusted accordingly. All such work shall be executed under the conditions of the original contract except that any claim for extension of time caused thereby shall be adjusted at the time of ordering such change.

In giving instructions, the *ENGINEER* shall have authority to make minor changes in the work, not involving extra cost, and not inconsistent with the purposes of the work, but otherwise, except in an emergency endangering life or property, no extra work or change shall be made

unless in pursuance of a written order from the *OWNER* signed or countersigned by the *ENGINEER*, or a written order from the *ENGINEER* stating that the *OWNER* has authorized the extra work or change, and no claim for an addition to the contract sum shall be valid unless so ordered. The value of any such extra work or change shall be determined in one or more of the following ways:

- (a) By estimate and acceptance in a lump sum
- (b) By unit prices named in the contract or subsequently agreed upon
- (c) By cost and percentage or by cost and a fixed fee

If none of the above methods is agreed upon, the *CONTRACTOR*, provided he receives an order as above, shall proceed with the work. In such case and also under case (c), he shall keep and present in such form as the Engineer may direct, a correct account of the cost, together with vouchers. In any case, the Engineer shall certify to the amount including reasonable allowance for overhead and profit, due to the *CONTRACTOR*. Pending final determination of value, payments on account of changes shall be made on the Engineer's certificate.

Should conditions encountered below the surface of the ground be at variance with the conditions indicated by the drawings and specifications, the contract sum shall be equitably adjusted upon claim by either party made within a reasonable time after the first observance of the conditions.

GP23. <u>DELETION OF WORK</u>

The *OWNER* has the right to delete any items that are a part of this contract.

GP24. DELAY AND EXTENSION OF TIME

If the *CONTRACTOR* should be delayed at any time in the progress of the work by any act or neglect of the *OWNER* or the *ENGINEER*, or of any employee of either, or by any separate *CONTRACTOR* employed by the *OWNER*, or by changes ordered in the work, or by strikes, lockouts, fire, unusual delay in transportation, unavoidable casualties or any causes beyond the *CONTRACTOR*'s control, or by delay authorized by the *ENGINEER* pending arbitration, or by any cause which the *ENGINEER* shall decide to justify the delay, then the time of completion shall be extended for such reasonable time as the *ENGINEER* may decide.

No such extension shall be made for delay occurring more than seven days before claim therefore is made in writing to the Engineer. In the case of continuing cause of delay, only one claim is necessary.

GP25. HOLIDAYS THAT WORK IS NOT PERMITTED

The CONTRACTOR may not perform work on this project on the following days:

- 1) Sundays
- 2) New Years Eve and New Years Day
- 3) Memorial Day
- 4) Independence Day

- 5) Labor Day
- 6) Thanksgiving Day and the day after Thanksgiving
- Christmas Eve and Christmas Day

GP26. **PERMITS**

Unless otherwise provided elsewhere in the Contract Documents, the CONTRACTOR shall obtain and pay for all construction permits and licenses.

GP27. UTILITIES

The CONTRACTOR shall be responsible for contacting and coordinating with all utilities affected by these project. The utilities shall be contacted prior to the pre-construction meeting, and informed of the date and location of this meeting. Contract working days will be charged unless the CONTRACTOR can show written evidence that he is making every possible effort on his part to get the utility work completed.

GP28. NON-DISCRIMINATION

In compliance with the Acts of Indiana General Assembly, 1933, Chapter 270, the CONTRACTOR hereby agrees:

That with respect to hire, tenure, terms, conditions, or privileges of employment of employees for the performance of work under this Contract or any Subcontract hereunder, no CONTRACTOR, Subcontractor, nor any person acting on behalf of such CONTRACTOR or subcontractor shall, by reason of race, color, religion, sex, national origin, or ancestry discriminate against any citizen qualified to do work to which the employment relates;

That no CONTRACTOR, Subcontractor, nor any person on his behalf shall, in any manner, discriminate against or intimidate any employee hired for the performance or work under this Contract on account of race, color, religion, sex, national origin, or ancestry;

That this Contract may be canceled or terminated by the OWNER, and all money due or to become due hereunder may be forfeited for a violation of the terms or conditions of this section of the Contract.

GP29. **INSURANCE**

CONTRACTOR'S Liability Insurance

The CONTRACTOR shall maintain such insurance as well as protect himself from claims under Workmen's Compensation Acts and other employee benefit acts; from claims for damages because of bodily injury, including death, to his employees and all others; and from claims for damages to property, any or all of which may arise out of or result from the CONTRACTOR'S operation under the contract, whether such operation be by himself or by any subcontractor, or anyone directly or indirectly employed by either of them. This insurance shall be written for not less than any limits of liability specified herein.

CONTRACTOR'S Insurance

The types and minimum amount of insurance to be provided for by the *CONTRACTOR* shall be as follows:

A) Workmen's Compensation and Occupational Disease Insurance

The *CONTRACTOR* shall provide Workmen's Compensation and Occupational Disease Insurance as required by law. Such policy shall specifically include coverage for the State of Indiana, and such adjoining states as required by the *CONTRACTOR'S* operations.

B) Employer's Liability Insurance

The *CONTRACTOR* shall provide Employer's Liability with minimum limits as follows:

\$100,000 bodily injury by accident, each accident; \$100,000 bodily injury by disease, each employee; \$100,000 bodily injury by disease, policy limit.

C) Comprehensive General Liability Insurance

The *CONTRACTOR* shall maintain a Comprehensive General Liability form of Insurance with a combined single limit for bodily injury and property damage of not less than \$1,000,000 each occurrence, \$2,000,000 annual aggregate. The insurance policy shall include the following:

- 1. Premises Operations: The policy shall include coverage for the following special hazards when applicable to the project.
 - a. Property damage arising out of blasting or explosion.
 - b. Property damage arising out of collapse of or structural injury to any building or structure due to grading of land, excavation, burrowing, filling, backfilling, tunneling, pile driving, cofferdam work or caisson work or moving, shoring, underpinning, raising or demolition of any building or structure or rebuilding of any structural support thereof.
 - c. Injury to or destruction of wires, conduits, pipes, mains, sewers and other similar property of any apparatus in connection therewith below the surface of ground, if caused by the use of mechanical equipment.
- 2. Contractual (Broad Form Indemnification): The *CONTRACTOR* agrees to indemnify and save harmless the *OWNER*, his agents and employees, from and against all loss or expense (including costs and attorneys' fees) by reason of liability imposed by law upon the *OWNER* for damages because of bodily injury, including death, at any time resulting there from sustained by any person or persons or on account of damage to property is due or claimed to be due to negligence of the *CONTRACTOR*, his subcontractors, employees or agents.
- 3. CONTRACTOR'S Protective: The CONTRACTOR shall maintain this type of

coverage on a "Blanket" basis to cover the operations of any subcontractors.

D) Automotive Liability Insurance

The *CONTRACTOR* shall maintain Comprehensive Automobile Liability Insurance policy with a combined single limit of not less than \$500,000. This coverage may be provided either as a separate policy or as part of the comprehensive liability policy described above. The automobile insurance must include coverage for all owned, non-owned, and hired vehicles.

E) Furnish Indiana State Forms No. 19 (Workmen's Compensation) and No. 105 (Occupational Disease Act).

F) Umbrella Insurance

The *CONTRACTOR* shall maintain an umbrella policy with limits of not less than \$1,000,000 per occurrence, \$1,000,000 aggregate in addition to their primary insurance.

GP30. ADDITIONAL INSURED

CONTRACTOR shall submit a "Certificate of Insurance" indicating the above necessary coverage as well as naming OWNER, its employees and representatives and ENGINEER as "Additional Insured" on all policies except Worker's Compensation.

GP31. PROOF OF INSURANCE

CONTRACTOR shall not commence work until he has obtained all insurance specified herein, has filed with the OWNER one (1) copy of Certificate of Insurance, and such insurance has been approved by the OWNER.

Should any coverage approach expiration during the Contract period, it shall be renewed prior to its expiration, and certificate again filed with the *OWNER*. If any of such policies are canceled or are changed so as to reduce the coverage evidenced by the Certificate, at least ten (10) days prior written notice by registered mail of such cancellation or change shall be sent to the *OWNER*.

All insurance provided for under this Section shall be written by Insurance Companies licensed to do business in Indiana and countersigned by registered Indiana agent. The insurance company shall file with the *OWNER*, one (1) copy of Affirmation of Authority, on the form furnished by the *OWNER*, as verification of the resident agent.

All insurance shall be maintained in full force and effect until the Contract has been fully and completely performed.

GP31. PARTIAL PAYMENTS

Partial payments will be made once each month as the work progresses. Said payments will be based upon estimates prepared by the *CONTRACTOR* using the provided FORM 8049 and a

County Claim Voucher and approved by the *ENGINEER* for the value of the work performed and materials complete in place in accordance with the contract, plans and specification. No partial payment will be made when the amount due the *CONTRACTOR* since the last estimate amounts to less than Five Hundred Dollars. From the total of the amount determined to be payable on a partial payment, ten percent of such total amount will be deducted and retained by the County until the final completion and acceptance of the work.

GP32. FINAL PAYMENT

When the contract work has been completed in an acceptable manner in accordance with the terms of the contract, the *CONTRACTOR* will prepare a final estimate for the work and will furnish the *ENGINEER* with a copy thereof. Before final payment of the contract, the *CONTRACTOR* shall furnish the provided Affidavit and Waiver of Lien from all subcontractors, material suppliers and equipment suppliers used in the prosecution the work. Final payment will not be made until a final inspection has been made, the work has been accepted by the County and has met the requirements of Section 109.08 of the Indiana Department of Transportation Standard Specifications. The *ENGINEER*, acting for the Board of County Commissioners, will then certify to the County Auditor the balance due the *CONTRACTOR*, and said certificate will be deemed an acceptance of the completed contract by the *OWNER*.

SPECIAL PROVISIONS

SP1. CONTRACT TIME

The schedule for the completion of the work included in this contract including incidentals and clean-up, shall be governed on a *Calendar Day Basis*.

The number of Calendar Days allowed for completion of Bridges 9, 14, 25, 95, 127, 134, 136, 174, and 197 shall be *(60) Calendar Days after issuance of Notice to Proceed.*

The **CONTRACTOR** shall limit the time that the road is closed to traffic to a maximum of **(60)** calendar days without written approval of an extension to this time from the **OWNER**.

SP2. <u>UTILITY INFORMATION</u>

All applicable sections of 105.06 and 107.18 shall apply except as amended elsewhere within the contract documents and as follows:

Coordination with any applicable utility is the sole responsibility of the CONTRACTOR.

The following is provided for information purposes only. The *CONTRACTOR* shall be responsible to contact the following personnel or company to coordinate his work prior to the commencement of any construction activities.

Bridge 9: Tri-County Telephone Co., Inc	Mr. Bill Miller	(765) 339-3533	William.miller@tdsrelecom.com
Bridge 14:			
AT&T Distribution	Mr. David Blackwell	(216) 543-0256	g09871@att.com
Charter Communications Marion	Mr. Dan Bielaczyc	(231) 941-3819	Dan.bielaczyc@charter.com
Tipmont REMC Fiber	Mr. Joe Kline	(765) 426-6170	jkline@tipmont.org
Tri-County Telephone Co., Inc	Mr. Bill Miller	(765) 339-3533	William.miller@tdsrelecom.com
Bridge 25:			
AT&T Distribution	Mr. David Blackwell	(216) 543-0256	g09871@att.com
Bridge 95:			
AT&T	David Blackwell	(216) 543-0256	g09871@att.com
Crawfordsville Electric Light & Power	Mr. Randy Hendrickson	(765) 307-2794	rhendrickson@celp.com
Tipmont REMC	Mr. Joe Kline	(765) 426-6170	jkline@tipmont.org

Bridge 127: AT&T Distribution Charter Communications Marion	Mr. David Blackwell Mr. Dan Bielaczyc	(216) 543-0256 (231) 941-3819	g09871@att.com Dan.bielaczyc@charter.com
Duke Energy	Mr. Don McDuffy	(317) 776-5320	Dei-dline-coord@duke- energy.com
Duke Energy Telecom	Mr. Chris Gee	(513) 287-1105	dukefibermw@duke-energy.com
Bridge 134:			
AT&T Distribution	Mr. David Blackwell	(216) 543-0256	g09871@att.com
Bridge 136:		(24.5) 242.0225	
AT&T Distribution	Mr. David Blackwell	(216) 543-0256	g09871@att.com
Bridge 174:			
AT&T	David Blackwell	(216) 543-0256	g09871@att.com
Endeavor Communications	Mr. Jason Lotz	(765) 795-5554	jlotz@weendeavor.com
Communications Corporation	Mr. Jeff Stanley	(765) 522-0113	Jeff.stanley@tdstelecom.com
Duke Energy	Mr. Don McDuffy	(317) 776-5320	Dei-dline-coord@duke- energy.com
Hendricks Power Cooperative	Mr. Jason Stewart	(317) 745-5473	jstewart@hendrickspower.com
MCI Communications	Mr. Dennis Rolland Craig	(317) 498-1242	dennis.craig@verizon.com
Roachdale Municipal Utility	Mr. Derick Wiggins	(812) 295-2800	dwiggins@midwesterneng.com
Bridge 197:			
Communications Corporation	Mr. Jeff Stanley	(765) 522-0113	Jeff.stanley@tdstelecom.com
Duke Energy	Mr. Don McDuffy	(317) 776-5320	Dei-dline-coord@duke- energy.com
Nucor Steel	Mr. Scott Siple	(765) 364-1323 x6472	Scott.siple@nucor.com
Parke County REMC	Mr. Matt Cosby	(765) 569-4232	mcosby@pcremc.com

SP3. **DISPOSAL OF EXCESS MATERIAL**

All excess material not to be salvaged (waste) shall be removed from the project site. Whether a private or public waste site is utilized, such disposal shall comply with all Federal, State and local ordinances and permit requirements. A copy of all permits obtained or applied for shall be submitted to the ENGINEER prior to the commencement of any construction activities.

The CONTRACTOR shall submit, in writing, the location of the proposed dump-site, for review, prior to the commencement of construction.

No direct payment will be made for this work but the cost thereof shall be included in the cost of the other items of the contract.

SP4. OPEN BURNING OF NATURAL GROWTH

Open burning of natural growth will not be permitted on this contract.

SP5. TREE AND LAWN PROTECTION

The *CONTRACTOR* shall use reasonable care for the protection of trees, shrubbery, and lawn areas beyond the permanent right-of-way.

SP6. EROSION CONTROL PLAN PAY ITEMS

The cost of all access and dewatering shown in the erosion control plans shall be included in the Stormwater Management Budget pay item.

SP7. DECREASED OR INCREASED QUANTITIES OF WORK

These Special Provisions shall not be considered as a waiver of, nor shall they invalidate the right of the *ENGINEER* to increase or decrease quantities of work.

SP8. TRAFFIC MAINTENANCE

The *CONTRACTOR* shall provide an access to all local homeowners at all times. If access is temporarily denied due to a construction activity, the *CONTRACTOR* shall coordinate the activity with the affected property owner.

SP9. <u>EXISTING CONDITIONS OF UTILITIES, ADDITIONAL RIGHT-OF-WAY, AND ENCROACHMENTS</u>

(a) Utilities

The status of all utility companies and organizations potentially involved with the work to be performed are described below as known at the time this contract was prepared.

Bridge 9

The facilities of <u>Tri-County Telephone Co.</u>, <u>Inc</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Bill Miller of the utility may be contacted at William.miller@tdsrelecom.com or (765) 339-3533.

Bridge 14

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at <u>g09871@att.com</u> or (219) 543-0256.

The facilities of <u>Charter Communications Marion</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Dan Bielaczyc of the utility may be contacted at Dan.bielaczyc@charter.com or (231) 941-3819.

The facilities of <u>Tipmont REMC Fiber</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Joe Kline of the utility may be contacted at <u>jkline@tipmont.org</u> or (765) 426-6170.

The facilities of <u>Tri-County Telephone Co.</u>, <u>Inc</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Bill Miller of the utility may be contacted at William.miller@tdsrelecom.com or (765) 339-3533.

Bridge 25

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at <u>g09871@att.com</u> or (219) 543-0256.

Bridge 95

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at <u>g09871@att.com</u> or (216) 543-0256.

The facilities of <u>Crawfordsville Electric Light & Power</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Randy Hendrickson of the utility may be contacted at rhendricson@celp.com or (765) 307-2794.

The facilities of <u>Tipmont REMC Fiber</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Joe Kline of the utility may be contacted at jkline@tipmont.org or (765) 426-6170.

Bridge 127

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at g09871@att.com or (219) 543-0256.

The facilities of <u>Charter Communications Marion</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Dan Bielaczyc of the utility may be contacted at Dan.bielaczyc@charter.com or (231) 941-3819.

The facilities of <u>Duke Energy</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Don McDuffy of the utility may be contacted at <u>dei-dline-coord@duke-energy.com</u> or (317) 776-5320.

The facilities of <u>Duke Energy Telecom</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Chris Gee of the utility may be contacted at <u>dukefibermw@duke-energy.com</u> or (513) 776-5320.

Bridge 134

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at <u>g09871@att.com</u> or (216) 543-0256.

Bridge 136

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at g09871@att.com or (216) 543-0256.

Bridge 174

The facilities of <u>AT&T</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, David Blackwell of the utility may be contacted at <u>g09871@att.com</u> or (216) 543-0256.

The facilities of <u>Endeavor Communications</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Jason Lotz of the utility may be contacted at <u>ilotz@weendeavor.com</u> or (765) 795-5554.

The facilities of <u>Communications Corporation</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Jeff Stanley of the utility may be contacted at <u>jeff.stanley@tdstelecom.com</u> or (765) 522-0113.

The facilities of <u>Duke Energy</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Don McDuffy of the utility may be contacted at <u>dei-dline-coord@duke-energy.com</u> or (317) 776-5320.

The facilities of <u>Hendricks Power Cooperative</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Jason Stewart of the utility may be contacted at jstewart@hendrickspower.com or (317) 745-5473.

The facilities of MCI Communications exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Dennis Rolland Craig of the utility may be contacted at <u>dennis.craig@verizon.com</u> or (317) 498-1242.

The facilities of <u>Roachdale Municipal Utility</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Derick Wiggins of the utility may be contacted at dwiggins@midwesterneng.com or (812) 295-2800.

Bridge 197

The facilities of <u>Communications Corporation</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Jeff Stanley of the utility may be contacted at <u>jeff.stanley@tdstelecom.com</u> or (765) 522-0113.

The facilities of <u>Duke Energy</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Don McDuffy of the utility may be contacted at <u>dei-dline-coord@duke-energy.com</u> or (317) 776-5320.

The facilities of <u>Nucor Steel</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Scott Siple of the utility may be contacted at scott.siple@nucor.com or (765) 364-1323 x6472.

The facilities of <u>Parke County REMC</u> exist within the project limits, but are not expected to be affected by the proposed construction. If questions arise, Matt Cosby of the utility may be contacted at mcosby@pcremc.com or (765) 569-4232.

(b) Right-of-Way

There are no Right-of-Way requirements for the contract.

(c) Encroachments

There is no involvement of encroachments for the contract.

SP10. STANDARD SPECIFICATIONS

Whenever in the contract documents the 2018, 2020, or 2022 Standard Specifications are referenced, it shall be interpreted to mean the 2024 Standard Specifications.

SP11. MAINTAINING PEDESTRIAN ACCESSIBILITY DURING CONSTRUCTION

Pedestrian accessibility shall be provided and maintained in accordance with 107.08 during the construction of the project where sidewalks and curb ramps exist. Pedestrian accessibility shall consist of the use of signed pedestrian detours utilizing existing and temporary features which shall include, but not be limited to, curb ramps, detectable warning surfaces, pedestrian signals, pavement markings, pedestrian phasing or sidewalks affected by the construction work zone. Pedestrian accessibility shall be as shown on the plans or as directed.

401 Indiana Department of Environmental Management Permits

404 US Army Corps of Engineering Coordination & Indiana Department of Natural Resources

Construction in a Floodway Permits

FOR

Bridge Scour Protection Maintenance

USACE Section 401 Permit Coordination

IDEM has issued the following Section 401 Permits for the proposed projects:

Bridge No.	IDEM Permit Numbers
9	LRL-2024-00125-sjk
14	LRL-2024-00124-sjk
25	LRL-2024-00134-jde
95	LRL-2024-00123-sjk
127	LRL-2024-00132-cte
134	LRL-2024-00139-cte
136	LRL-2024-00133-jde
174	LRL-2024-00136-jde
197	LRL-2024-00137-cte

USACE Section 404 Permit Coordination

After review of the projects listed above, they have been verified to meet the US Army Corps of Engineers (USACE) Section 404 Regional General Permit Conditions. No additional coordination is necessary.

IDNR CIF Permit Coordination


IDNR has issued the following Construction in a Floodway permits for the proposed Projects:

Bridge No.	IDEM Permit Numbers
25	LRL-2024-00134-jde
197	LRL-2024-00137-cte

County Map

FOR

Bridge Scour Protection Maintenance



Bridge Inspection Reports

FOR

Bridge Scour Protection Maintenance

The following bridge inspection reports are provided for information only.



South Approach Looking North




Looking at Undercutting of End Bent at Northeast Corner



East Face Looking Downstream



Looking at Spall and Delamination at East Face



East Face Looking Downstream

ASSET NAME: 54-00009

IDENTIFICATION	<u>N</u>	AGE OF SERVICE		LOAD RATING AND PO	STING
1. State:	 185 - Indiana	27. Year Built:	1973	31. Design Load:	
2. District:	01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	48 Tor
3. County:		42. Type of Service:		66. Inventory Rating:	36 Tor
4. Place Code:	00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	22 Tor
6. Features Intersected:	NORTH FORK OF COAL CREEK	B. Under Bridge	5 - Waterway	70. Bridge Posting: 5 - Equal to o	r above legal load
7. Facility Carried:	CR 575W	28. Lanes		41. Open, Posted, or Closed:	A - Ope
8. NBI #:	5400006	A. On Bridge:	2	66C. Tons Posted:	Tor
9. Location:	01.00 E of CR 900 N	B. Under Bridge:	0	66D. Date Posted/Closed:	
16. Latitude	40.18553 Decimal Degrees	29. ADT:	150 VPD	INSPECTIONS	
17. Longitude	87.01311 Decimal Degrees	30. ADT Year:	2022	INSPECTIONS 90. Inspection Date:	04/27/202
CTDUCTURE TV	DE	109. ADTT:	6 %	91. Des. Inspection Frequency	
43. Structure Type – Main:	PE.	GEOMETRIC DATA		92. Critical Feature Inspected:	24 IVIOLIUI
	2 - Concrete continuous	48. Maximum Span Length	24 0 Et	A N Mos. B N Mos.	C. N.Mo.
		49. Total Structure Length:		93. Critical Feature Inspection Date:	C IN IVIO
44. Structure Type – Approach		50A. Sidewalk/Curb Left:		45. Critical realure inspection date. A:	C.
	0 - Other	50A. Sidewalk/Curb Right:		А	C
	0 - Other	51. Bridge Roadway Width: (Curb-Curb):		PROPOSED IMPROVE	<u>MENTS</u>
31	3	52. Deck Width (0-0):		97. Year Needed:	
•				75A. Type Work:	
		32. Approach Roadway Width:			
- ·		47. Total Horizontal Clearance		76. Improvement Length:	0.0 F
108. Wearing Surface / Protec		53. Vertical Clearance over Deck:		94. Bridge Improvement Cost	0 x 100
	1 - Monolithic Concrete			95. Roadway Improvement Cost	0 x 100
	0 - None	54. Min. Vertical Underclearance:		96. Total Project Cost:	0 x 100
C. Deck Protection	0 - None	55. Min. Lateral Underclearance - Right:		Sufficiency Rating (Unofficial)	92
CONDITION					
_	CONDITION / MATERIAL				<u>ratin</u>
		WEXP REBAR W/SECTION LOSS UP TO 25% M			
· ·		laterial: CONCRETE			
		L BOTTOM, DELAMS ALONG COPINGS Materia			
		RTH PIER, NO FOOTING EXPOSED,CRACKS W			
		ON Material: NATURAL/RIPRAP			
62. Culvert:	I/A Material: N/A				N
<u>APPRAISAL</u>					RATIN
67. Structural:					
,					
	DEFICIENCES				RATIN
_					
72. Roadway Alignment: R					
	RUTTED SETTI ED AT RRINGE END	Material: RITHMINOHS (72): SERIOHS.SHARD (CURVENTEVEL		7

EXECUTIVE SUMMARY

NO MAJOR WORK NEEDED.RECOMMEND INSTALLING CURRENT BRIDGE AND APPROACH RAIL, FILLING SHOULDER EROSION WITH STONE AND RIPRAP, PLACING RIPRAP AT NORTH PIER, AND PLACING BEM AT SOUTHEAST, SOUTHWEST, AND NORTHEAST (2022) NORTHEAST CORNER OF BENT 1 UNDERCUT, 2 FT SCOUR HOLE AT UPSTREAM NOSE OF PIER 3, EROSION AT ALL 4 CORNERS OF STRUCTURE. TREES GROWING BENEATH STRUCUTRE. SPALLING AND DELAMINATION OCCURING AT OUTER EDGE OF SLAB ON BOTTOM OF BOTH EAST AND WEST FACE. RECOMMENDED MAINTENANCE IN 2023: PLACE RIPRAP AT ALL FOUR CORNERS OF STRUCTURE TO PREVENT FURTHER EROSION. REMOVE TREES FROM BENEATH STRUCTURE



South Approach Looking North




Looking at Large Spall With Exposed Reinforcement



West Face Looking Downstream



Looking at Asphalt Patch and Spall



ASSET NAME: 54-00014

<u>IDENTIFICATIO</u>	-	AGE OF SERVICE		LOAD RATING AND	
	185 - Indiana	27. Year Built:		31. Design Load:	
2. District:	01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	
•	054 - MONTGOMERY	42. Type of Service:		66. Inventory Rating:	
4. Place Code:	00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	22 Ton
6. Features Intersected:	LITTLE POTATO CREEK	B. Under Bridge	5 - Waterway	70. Bridge Posting: 5 - Equa	I to or above legal load
7. Facility Carried:	CR 700E	28. Lanes		41. Open, Posted, or Closed:	A - Ope
8. NBI #:	5400009	A. On Bridge:	2	66C. Tons Posted:	Ton
9. Location:	00.10 N of CR 85 N	B. Under Bridge:	0	66D. Date Posted/Closed:	
16. Latitude	40.16596 Decimal Degrees	29. ADT:	850 VPD	INSPECTIONS	
17. Longitude	86.77103 Decimal Degrees	30. ADT Year:	2022	90. Inspection Date:	04/20/202
STRUCTURE T	/DE	109. ADTT:	12 %	91. Des. Inspection Frequency	
	<u> </u>	CEOMETRIC DATA			24 IVIOHUI
43. Structure Type – Main:	2	GEOMETRIC DATA	2/ 0 51	92. Critical Feature Inspected:	4 O N.M
	2 - Concrete continuous	48. Maximum Span Length		A	/los. C:N Mos
	01 - Slab	49. Total Structure Length:		93. Critical Feature Inspection Date:	•
44. Structure Type – Approa		50A. Sidewalk/Curb Left:		A: B:	C:
	0 - Other	50B. Sidewalk/Curb Right:		PROPOSED IMPROV	VEMENTS
,, ,	00 - Other	51. Bridge Roadway Width: (Curb-Curb):		97. Year Needed:	
	3	52. Deck Width (o-o):		75A. Type Work:	
	0000	32. Approach Roadway Width:			
107. Deck Type:	1 - Concrete Cast-in-Place	34. Skew:	0 Degree(s)	76. Improvement Length:	0 F
108. Wearing Surface / Prote	ection System	47. Total Horizontal Clearance	25.0 Ft.	94. Bridge Improvement Cost	
A. Wearing Surface	1 - Monolithic Concrete	53. Vertical Clearance over Deck:	99.99 Ft.	95. Roadway Improvement Cost	
B. Deck Membrane	0 - None	54. Min. Vertical Underclearance:		96. Total Project Cost:	
C. Deck Protection	0 - None	55. Min. Lateral Underclearance - Right:	0.0 Ft.	Sufficiency Rating (Unofficial)	
		56. Min. Lateral Underclearance - Left:	0.0 Ft.	Suniciency Nating (Ononicial)	01.
CONDITION					
	CONDITION / MATERIAL				RATINO
58. Deck:		RANS CRACKS, 8'x2.5' SPALL IN CENTER SPA	N PARTIALLY PATCH	HED WITH ASPHALT Material: CONT. CON	ICRETE SLAB6
		SPALL IN CENTER SPAN PARTIALLY PATCHE			
•		LONG SPAN 3 EAST COPING WITH EXPOSED			
		EGING SI AN O ENG! GOI ING WITH EAR GOLD			
		I: CONCRETE PIER & ABUTMENTS			
		NIMAL RIPRAP Material: NATURAL/RIPRAP			
		WINAL KIEKAE Waterial. WATOKALIKIEKAE			
	TVA Material IVA				IN
<u>APPRAISAL</u>					RATINO
67. Structural:					
,					
69. Underclearance:					
69. Underclearance:	DEFICIENCES				RATINO
	DEFICIENCES APPEARS ADEQUATE				<u>RATINO</u>
71. Waterway Adequacy:	APPEARS ADEQUATE	T Material: BITUMINOUS (72): VERY GOOD-ST			6

EXECUTIVE SUMMARY

LARGE BITUMINOUS PATCHING IN DECK. HEAVY DETERIORATION AT DECK DRAINS. EROSION AROUND PIERS. MINIMAL PROTECTION OF BENTS RECOMMEND CLEANING GUTTERS, REPACING BITUMINOUS DECK PATCH WITH EPOXY MODIFIED CONCRETE PATCH, SEALING BRIDGE DECK, ADDING RIPRAP ON SPLILLSLOPES AND AROUND PIERS, AND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING.



South Approach Looking North




Looking at End Bent 5



West Face Looking Upstream



Looking at Spall at Beam Ends Pier 2 West Face



ASSET NAME: 54-00025

<u>IDENTIFICATI</u>	ON	AGE OF SERVICE		LOAD RATING AND	POSTING
•		27. Year Built:	1969	31. Design Load:	
2. District:	01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	48 Tons
3. County:		42. Type of Service:		66. Inventory Rating:	36 Tons
4. Place Code:	00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	
6. Features Intersected:	SUGAR CREEK	B. Under Bridge	5 - Waterway	70. Bridge Posting:5 - Equa	
7. Facility Carried:	CR 700E	28. Lanes	-	41. Open, Posted, or Closed:	A - Open
8. NBI #:	5400018	A. On Bridge:	2	66C. Tons Posted:	Tons
9. Location:	00.80 S of CR 650 N	B. Under Bridge:	0	66D. Date Posted/Closed:	
16. Latitude		29. ADT:	940 VPD	INSPECTIONS	
17. Longitude	86.77205 Decimal Degrees	30. ADT Year:	2022	INSPECTIONS 90. Inspection Date:	05/04/2022
STRUCTURE 1	TVDE	109. ADTT:	13 %	91. Des. Inspection Frequency	
·		GEOMETRIC DATA		92. Critical Feature Inspected:	24 IVIOTILIS
43. Structure Type – Main:	6 - Prestressed concrete continuous		72.0 E+	A	Acc C: N.Moc
	02 - Stringer/Multi-beam or Girder	48. Maximum Span Length49. Total Structure Length:		93. Critical Feature Inspection Date:	105. C IN IVIUS.
		50A. Sidewalk/Curb Left:		4: B:	C.
44. Structure Type – Appro	0 - Other	50A. Sidewalk/Curb Right:			
	0 - Other	51. Bridge Roadway Width: (Curb-Curb):		PROPOSED IMPROV	<u>/EMENTS</u>
,,	4	52. Deck Width (o-o):		97. Year Needed:	
· ·	ach:	32. Approach Roadway Width:		75A. Type Work:	
	1 - Concrete Cast-in-Place	34. Skew:			
		47. Total Horizontal Clearance	• • • •	76. Improvement Length:	0 Ft.
108. Wearing Surface / Pro	=	53. Vertical Clearance over Deck:		94. Bridge Improvement Cost	
=		53. Vertical Clearance over Deck:		95. Roadway Improvement Cost	0 x 1000
	0 - None	55. Min. Lateral Underclearance - Right:		96. Total Project Cost:	0 x 1000
C. Deck Protection	u - None	55. Min. Lateral Underclearance - Right: 56. Min. Lateral Underclearance - Left:		Sufficiency Rating (Unofficial)	90.9
		56. Milli. Lateral Underclearance - Lert	U.U Fl.		
CONDITION					
OONDITION	CONDITION / MATERIAL				RATING
58. Deck:		WORN, POPOUTS ON SURFACE, UNDERSIDE	COOD Material: CON	CRETE (8")	
		TH PATCHES ALONG CENTERLINE IN SOUTH			
		S AT BEAM ENDS AT PIER DIAPHRAGM Mate			
•		JAT DEAM ENDJAT FIER DIAI FIRAGIN MAIC			
		ERS, DIRT ON ABUTMENT SEATS, JOINTS AE			
		E EROSION, DRIFT AT PIERS, ERODING SLIG			
	IW/ Civatorian IW/ C				
<u>APPRAISAL</u>					
					RATING
67. Structural:					7
68. Geometry:					5
69. Underclearance:					N
	<u>DEFICIENCES</u>				RATING
, , ,					
, ,		AT EDGES, MANY CRACKS Material: BITUMI			
113. Scour Rating	STABLE - WITHIN LIMITS			5 - Scour within lim	its of footing or piles

EXECUTIVE SUMMARY

RECOMMEND ADDING RIPRAP ON SOUTH SPILLSLOPE, CLEARING DRIFT FROM PIERS AND SPAN 2, PATCHING DECK SPALLS WITH EPOXY MODIFIED CONCRETE, SEALING BRIDGE DECK FOR CRACKS, REGROUTING OUTSIDE BEAM ENDS OVER PIERS, REPLACING JOINTS AT ABUTMENTS, ANDINSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITHBRIDGE END MARKERS (2022)-RECOMMEND ADDING RIPRAP ON SOUTH SPILLSLOPE, CLEARING DRIFT FROM PIERS AND SPAN 2, PATCHING DECK SPALLS WITH EPOXY MODIFIED CONCRETE, SEALING BRIDGE DECK FOR CRACKS, REGROUTING OUTSIDE BEAM ENDS OVER PIERS, REPLACING JOINTS AT ABUTMENTS, ANDINSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITHBRIDGE END MARKERS. REMOVE VEGITATION FROM BENEATHE STRUCTURE.



East Approach to Structure - Looking West




Looking at Bent 2



North Face of Structure - Looking Downstream



Looking at Deck Note-Transverse Cracks over Bent 3



ASSET NAME: 54-00095

<u>IDENTIFICATION</u>	AGE OF SERVICE		LOAD RATING AND POSTI	NG
1. State:	27. Year Built:	1998	31. Design Load:	5 - HS 2
2. District: 01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	
3. County:	42. Type of Service:		66. Inventory Rating:	
4. Place Code:00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	34 Ton
6. Features Intersected: BLACK CREEK	B. Under Bridge	5 - Waterway	70. Bridge Posting:5 - Equal to or above	e legal load:
7. Facility Carried: CR 80N	28. Lanes		41. Open, Posted, or Closed:	A - Oper
8. NBI #:5400077	A. On Bridge:	2	66C. Tons Posted:	Ton:
9. Location:00.10 E of CR 300 W	B. Under Bridge:	0	66D. Date Posted/Closed:	
16. Latitude	29. ADT:	200 VPD	INSPECTIONS	
17. Longitude86.95970 Decimal Degrees	30. ADT Year:	2022	90. Inspection Date:	05/12/202
STRUCTURE TYPE	109. ADTT:	6 %	91. Des. Inspection Frequency	
43. Structure Type – Main:	GEOMETRIC DATA		92. Critical Feature Inspected:	24
A. Material	48. Maximum Span Length	41 0 E+	A	N Moc
B. Type of Design	49. Total Structure Length:		93. Critical Feature Inspection Date:	IN IVIOS
44. Structure Type – Approach:	50A. Sidewalk/Curb Left:		A: B: C:	
44. Structure Type – Approach: A. Material			A: B: C:	
	50B. Sidewalk/Curb Right:51. Bridge Roadway Width: (Curb-Curb):		PROPOSED IMPROVEMEN	
B. Type of Design			97. Year Needed:	
45. No. of Spans – Main:	52. Deck Width (0-0):		75A. Type Work:	
46. No. of Spans – Approach:	32. Approach Roadway Width:			
3.	47. Total Horizontal Clearance	3 17	76. Improvement Length:	0.0 F1
108. Wearing Surface / Protection System			94. Bridge Improvement Cost	0 x 100
A. Wearing Surface1 - Monolithic Concrete	53. Vertical Clearance over Deck:		95. Roadway Improvement Cost	0 x 100
B. Deck Membrane	54. Min. Vertical Underclearance:		96. Total Project Cost:	0 x 100
C. Deck Protection 1 - Epoxy Coated Reinforcing	55. Min. Lateral Underclearance - Right: 56. Min. Lateral Underclearance - Left:		Sufficiency Rating (Unofficial)	100.0
CONDITION				
CONDITION / MATERIAL				RATING
58. Deck: GOOD-TRANS HAIRLINE CRACKS A	T EDGES, LONG. HAIRLINE CRACKS AT ENDS	, PATTERN HAIRLINE	CRACKS OVER PIERS Material: 20" CRC SLAB	7
	NE CRACKS, WORN, POPOUTS Material: CON	CRETE		
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI				6
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE	EADS, MINOR HONEYCOMBING, SPALL AT MID	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6 7
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure:	ADS, MINOR HONEYCOMBING, SPALL AT MIE	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6 7 N/A
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M	ADS, MINOR HONEYCOMBING, SPALL AT MIE INOR HONEYCOMBING Material: CONCRETE E	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6 7 N/A
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint N/A 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES	ADS, MINOR HONEYCOMBING, SPALL AT MIE INOR HONEYCOMBING Material: CONCRETE F T BANK, DRIFT AT BENT 2 Material: RIPRAP/G	OSPAN IN SPAN B AT END BENTS-PILE BEN ABIONS	SOUTH COPING Material: 20" CRC SLABTS.	6 7 N/A 7
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint. N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A.	ADS, MINOR HONEYCOMBING, SPALL AT MIE INOR HONEYCOMBING Material: CONCRETE F T BANK, DRIFT AT BENT 2 Material: RIPRAP/G	OSPAN IN SPAN B AT END BENTS-PILE BEN ABIONS	SOUTH COPING Material: 20" CRC SLABTS.	6 7 N/A 7
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint N/A 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A	EADS, MINOR HONEYCOMBING, SPALL AT MIE INOR HONEYCOMBING Material: CONCRETE F T BANK, DRIFT AT BENT 2 Material: RIPRAP/G	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLABTS	67776N
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint. N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural:	ADS, MINOR HONEYCOMBING, SPALL AT MIE	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6776N RATING
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint. N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural: 68. Geometry:	ADS, MINOR HONEYCOMBING, SPALL AT MIE	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6776N RATING7
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural: 68. Geometry: 69. Underclearance:	ADS, MINOR HONEYCOMBING, SPALL AT MIE	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	6776N RATING76
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint. N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural: 68. Geometry: 69. Underclearance: DEFICIENCES	ADS, MINOR HONEYCOMBING, SPALL AT MIE	OSPAN IN SPAN B AT	SOUTH COPING Material: 20" CRC SLAB	676N RATING76
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint. N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural: 68. Geometry: 69. Underclearance: DEFICIENCES 71. Waterway Adequacy: APPEARS ADEQUATE	ADS, MINOR HONEYCOMBING, SPALL AT MIE	END BENTS-PILE BEN GABIONS	SOUTH COPING Material: 20" CRC SLAB	676N RATINO76N RATINO7
58.01. Wearing Surface: SATISFACTORY-NUMEROUS HAIRLI 59. Superstructure: GOOD-DELAMINATIONS AT DRIP BE Paint N/A. 60. Substructure: GOOD-SURFACE RUST ON PILES, M 61. Channel: SATISFACTORY-FLOW ALONG WES 62. Culvert: N/A Material: N/A. APPRAISAL 67. Structural: 68. Geometry: 69. Underclearance:	EADS, MINOR HONEYCOMBING, SPALL AT MIE INOR HONEYCOMBING Material: CONCRETE F T BANK, DRIFT AT BENT 2 Material: RIPRAP/G	OSPAN IN SPAN B AT END BENTS-PILE BEN ABIONS UMINOUS (72): SATIS	TS	676767767676

EXECUTIVE SUMMARY

RECOMMENDCLEARING SMALL TREES UNDER BRIDGE, CLEARING DRIFT, AND CLEANING AND PAINTING PILES. INSTALL BEM ON NW CORNER



West Approach Looking East




South Face Looking Downstream



Looking at East Face Pier 2



Looking at Undercutting at End Bent 4



North Face Looking Downstream

ASSET NAME: 54-00127

1 Chala		AGE OF SERVICE	40/5	LOAD RATING AND POST	
		27. Year Built:		31. Design Load:	
	01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	
,		42. Type of Service:	4	66. Inventory Rating:	
		A. On Bridge	0 ,	66B. Inventory Rating (H):	
	OFFIELD CREEK	B. Under Bridge	5 - Waterway	70. Bridge Posting: 5 - Equal to or ab	_
•	CR 400S	28. Lanes	•	41. Open, Posted, or Closed:	•
	5400100	A. On Bridge:		66C. Tons Posted:	
		B. Under Bridge:		66D. Date Posted/Closed:	
	39.98146 Decimal Degrees	29. ADT:		<u>INSPECTIONS</u>	
17. Longitude	86.90365 Decimal Degrees	30. ADT Year:		90. Inspection Date:	05/11/202
STRUCTURE '	TYPE	109. ADTT:	5 %	91. Des. Inspection Frequency	24 Month
43. Structure Type – Main	:	GEOMETRIC DATA		92. Critical Feature Inspected:	
A. Material	2 - Concrete continuous	48. Maximum Span Length	21.0 Ft.	A	N Mos
B. Type of Design	01 - Slab	49. Total Structure Length:		93. Critical Feature Inspection Date:	
44. Structure Type – Appr		50A. Sidewalk/Curb Left:		A: B: C:.	
A. Material	0 - Other	50B. Sidewalk/Curb Right:	0.7 Ft.	DDODOCED IMPROVEM	ENITO
B. Type of Design		51. Bridge Roadway Width: (Curb-Curb):	24.0 Ft.	PROPOSED IMPROVEMI	
45. No. of Spans – Main:	3	52. Deck Width (o-o):		97. Year Needed:	
· ·	ach:0000	32. Approach Roadway Width:	20.0 Ft.	75A. Type Work:	
	1 - Concrete Cast-in-Place	34. Skew:		77.1	0.05
108. Wearing Surface / Pr		47. Total Horizontal Clearance	•	76. Improvement Length:	
-	1 - Monolithic Concrete	53. Vertical Clearance over Deck:	99.99 Ft.	94. Bridge Improvement Cost	
-	0 - None	54. Min. Vertical Underclearance:		95. Roadway Improvement Cost	
C. Deck Protection	0 - None	55. Min. Lateral Underclearance - Right:		96. Total Project Cost:	
		56. Min. Lateral Underclearance - Left:		Sufficiency Rating (Unofficial)	90.9
CONDITION					
	CONDITION / MATERIAL				RATING
58. Deck:		I. TRANSVERSE CRACKS, POPOUTS, GRAVE	L ALONG CURBS Mate	erial: CONCRETE	6
-					
				, SEEPAGE Material: CONCRETE CAP ON PILES	
				Material: CONCRETE & RIPRAP	
<u>APPRAISAL</u>					
/7 Christinal					RATINO
,					
оу. Underclearance:					
74 14/1	<u>DEFICIENCES</u>				RATING
, ,				70) 04 7074 0 700	
	CVUCEVLLUDA CDVCKED EDUCIU	N SE CORNER SETTIEN TRANSCRACKS M	aterial: RITHMINOHS (72): SATISFACTORY-INTERSECTION E, RISE W	6

EXECUTIVE SUMMARY

RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING AND BRIDGE END MARKERS, BACKFILLING UNDERMINED AREAS, PLACING RIPRAP AT TOE OF SLOPEWALLS & AT CORNERS OF BRIDGES TO STABILIZE EROSION, AND REMOVING VEGETATION FROM UNDER BRIDGE.



North Approach Looking South




Looking at End Bent 1



East Face Looking Downstream



Looking at Delamination Along East Coping Full Length



ASSET NAME: 54-00134

IDENTIFICATION 1. State:	185 - Indiana	AGE OF SERVICE 27. Year Built:	1975	LOAD RATING AND PO	
2. District:		106. Reconstructed:		64. Operating Rating:	
3. County:		42. Type of Service:		66. Inventory Rating:	
4. Place Code:		A. On Bridge	1 - Highway	66B. Inventory Rating (H):	
6. Features Intersected:		B. Under Bridge	0 ,	70. Bridge Posting: 5 - Equal to	
7. Facility Carried:		28. Lanes		41. Open, Posted, or Closed:	=
8. NBI #:		A. On Bridge:	2	66C. Tons Posted:	
9. Location:	00.30 N of CR 500 S	B. Under Bridge:		66D. Date Posted/Closed:	
16. Latitude	39.9717 Decimal Degrees	29. ADT:		INCREATIONS	
17. Longitude	86.88449 Decimal Degrees	30. ADT Year:	2022	INSPECTIONS On Improvious Date:	05/11/202
CTDUCTURE TVD	•	109. ADTT:	5 %	90. Inspection Date:	
STRUCTURE TYPI	<u> </u>	GEOMETRIC DATA			24 IVIOHUI
43. Structure Type – Main:	2 - Concrete continuous	GEOMETRIC DATA 48. Maximum Span Length	22 O E+	92. Critical Feature Inspected: A N Mos. B N Mos	C. N.Moo
	2 - Concrete continuous	49. Total Structure Length:		93. Critical Feature Inspection Date:	. C IN IVIUS
44. Structure Type – Approach:	UI - SIAD	50A. Sidewalk/Curb Left:		93. Chiicai Feature inspection date: A:	C·
ži	0 - Other	50B. Sidewalk/Curb Right:			
	00 - Other	51. Bridge Roadway Width: (Curb-Curb):		PROPOSED IMPROVE	<u>MENTS</u>
45. No. of Spans – Main:		52. Deck Width (o-o):		97. Year Needed:	
46. No. of Spans – Approach:		32. Approach Roadway Width:		75A. Type Work:	
107. Deck Type:		34. Skew:			
108. Wearing Surface / Protection		47. Total Horizontal Clearance	•	76. Improvement Length:	
=	1 - Monolithic Concrete	53. Vertical Clearance over Deck:		94. Bridge Improvement Cost	
•	0 - None	54. Min. Vertical Underclearance:		95. Roadway Improvement Cost	
	0 - None	55. Min. Lateral Underclearance - Right:		96. Total Project Cost:	
O. DOURT TOLOGUETE	THORIO	56. Min. Lateral Underclearance - Left:		Sufficiency Rating (Unofficial)	99.0
CONDITION CON	IDITION / MATERIAL				RATINO
·		Material: CONCRETE			6
		GRAVEL ON DECKS. MAP CRACKING Material			
		MINATIONS AT DRIP BEADS, VERTICAL COPIN			
		·			
60. Substructure: GOC	DD-LIGHT SCALING, NORMAL WI	EAR. HAIRLINE VERTICAL CRACKS Material: (CONCRETE PIER & E	ND BENTS	7
61. Channel:SAT	ISFACTORY-MODERATE EROSIC	ON, DRIFT UPSTREAM AND DOWNSTREAM. N	O FOOTING EXPOSU	RE Material: NATURAL/RIPRAP	6
62. Culvert:	Material: N/A				N
ADDDAICAI					
<u>APPRAISAL</u>					RATINO
67 Structural:					
67. Structural:					
68. Geometry:					IN
68. Geometry:					₽∆TINI
68. Geometry:	<u>ICIENCES</u>				RATINO 7
68. Geometry:	ICIENCES FEARS ADEQUATE	al: BITUMINOUS (72): VERY GOOD-STRAIGHT,			7

EXECUTIVE SUMMARY

NORMAL SERVICE WEAR OF DECK AND SUBSTRUCTURE. RECOMMEND UPDATING RAILING FEATURES TO CURRENT STANDARDS.REPLACE BRIDGE END MARKER AT NW CORNER. PLACE RIPRAP AROUND PIERS AND UP SPILLSLOPES.



South Approach Looking North






Looking at North Face Pier 2



Lookign at Spall on Coping Span A



East Face Looking Downstream

ASSET NAME: 54-00136

IDENTIFICATI 1. State:	185 - Indiana	AGE OF SERVICE 27. Year Built:	197⊿	LOAD RATING AND PO	
	01 - Crawfordsville	106. Reconstructed:		64. Operating Rating:	
		42. Type of Service:		66. Inventory Rating:	
-	00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	
	OFFIELD CREEK	B. Under Bridge		70. Bridge Posting: 5 - Equal to	
	CR 200E	28. Lanes		41. Open, Posted, or Closed:	•
-	5400105	A. On Bridge:	2	66C. Tons Posted:	-
		B. Under Bridge:		66D. Date Posted/Closed:	
16. Latitude		29. ADT:			
	86.86568 Decimal Degrees	30. ADT Year:		INSPECTIONS	07/44/000
· ·	· ·	109. ADTT:	12 %	90. Inspection Date:	
STRUCTURE 1				91. Des. Inspection Frequency	24 Months
43. Structure Type – Main		GEOMETRIC DATA		92. Critical Feature Inspected:	
	2 - Concrete continuous	48. Maximum Span Length		A N Mos. B N Mos	. C: N Mos
	01 - Slab	49. Total Structure Length:		93. Critical Feature Inspection Date:	
44. Structure Type – Appro		50A. Sidewalk/Curb Left:		A: B:	C:
	0 - Other	50B. Sidewalk/Curb Right:		PROPOSED IMPROVE	MENTS
, · · · · ·	00 - Other	51. Bridge Roadway Width: (Curb-Curb):		97. Year Needed:	
	3	52. Deck Width (o-o):		75A. Type Work:	
	ach: 0000	32. Approach Roadway Width:		31.	
	1 - Concrete Cast-in-Place	34. Skew:	•	76. Improvement Length:	0.0 Ft
108. Wearing Surface / Pro	rotection System	47. Total Horizontal Clearance		94. Bridge Improvement Cost	
•	1 - Monolithic Concrete	53. Vertical Clearance over Deck:	99.99 Ft.	95. Roadway Improvement Cost	
B. Deck Membrane	0 - None	54. Min. Vertical Underclearance:		96. Total Project Cost:	
C. Deck Protection	0 - None	55. Min. Lateral Underclearance - Right:	0.0 Ft.	Sufficiency Rating (Unofficial)	
		56. Min. Lateral Underclearance - Left:	0.0 Ft.	Sunicioney ruling (orioincial)	
CONDITION					
CONDITION	CONDITION / MATERIAL				RATING
58 Dock		WORN Material: CONCRETE			-
		E PATTERN CRACKS, WORN Material: CONCR			
•		MINATIONS ALONG COPINGS, HAIRLINE LON			
		WINATIONS ALONG COLINGS, TIAINLINE LON			
		CKING WITH EFFL. IN PIERS, NORTHEAST WII			
		EXPANSION EROSION DOWNSTREAM Materia			
		EXPANSION EROSION DOWNS I REAW INICIO			
	IN/A IVIALEITAI. IV/A				N
<u>APPRAISAL</u>					RATING
67 Structural					<u>KATING</u>
,					N
J7. UNUTICIEALANCE	DEFICIENCES				RATING
	<u>DELIGITIVOES</u>				MIING

EXECUTIVE SUMMARY

NORMAL SERVICE WEAR. SUPERSTRUCTURE AND SUBSTRUCTURE WITH MINOR CRACKING. MODERATE EROSION ALONG CHANNEL, SOME SCOUR HOLES ALONG PIERS WITH NO FOOTING EXPOSURE. RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING, INSTALLING BRIDGE END MARKERS TO SOUTH, AND CLEARING GRAVEL FROM DECK. PLACE RIPRPAP AROUND PIERS.

71. Waterway Adequacy: APPEARS BARELY ADEQUATE.......



North Approach Looking South




Looking at End Bent 1



East Face Looking Downstream



Looking at Undercutting at End Bent 4 with Exposed Pile



ASSET NAME: 54-00174

IDENTIFICATION	AGE OF SERVICE		LOAD RATING AND PO	STING
1. State:	27. Year Built:	1967	31. Design Load:	
2. District: 01 - Crawfordsville	106. Reconstructed:	0	64. Operating Rating:	
3. County:	42. Type of Service:		66. Inventory Rating:	
4. Place Code:	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	
6. Features Intersected: HAW CREEK	B. Under Bridge		70. Bridge Posting: 5 - Equal to	
7. Facility Carried:CR 550E	28. Lanes	•	41. Open, Posted, or Closed:	A - Ope
8. NBI #:	A. On Bridge:	2	66C. Tons Posted:	Ton
9. Location:	B. Under Bridge:	0	66D. Date Posted/Closed:	
16. Latitude 39.87891 Decimal Degrees	29. ADT:	2200 VPD	INSPECTIONS	
17. Longitude86.79897 Decimal Degrees	30. ADT Year:	2022	90. Inspection Date:	05/02/202
STRUCTURE TYPE	109. ADTT:	13 %	91. Des. Inspection Frequency	
43. Structure Type – Main:	GEOMETRIC DATA		92. Critical Feature Inspected:	24 101011111
A. Material 2 - Concrete continuous	48. Maximum Span Length	26 N Et	A N Mos. B N Mos.	C: N Mos
B. Type of Design01 - Slab	49. Total Structure Length:		93. Critical Feature Inspection Date:	C IN IVIOS
44. Structure Type – Approach:	50A. Sidewalk/Curb Left:		A: B:	C:
A. Material 0 - Other	50B. Sidewalk/Curb Right:			
B. Type of Design	51. Bridge Roadway Width: (Curb-Curb):		PROPOSED IMPROVE	
45. No. of Spans – Main:	52. Deck Width (o-o):		97. Year Needed:	
46. No. of Spans – Approach:	32. Approach Roadway Width:		75A. Type Work:	
107. Deck Type:1 - Concrete Cast-in-Place	34. Skew:			
108. Wearing Surface / Protection System	47. Total Horizontal Clearance	0 17	76. Improvement Length:	
A. Wearing Surface	53. Vertical Clearance over Deck:		94. Bridge Improvement Cost	
B. Deck Membrane	54. Min. Vertical Underclearance:		95. Roadway Improvement Cost	
C. Deck Protection 0 - None	55. Min. Lateral Underclearance - Right:		96. Total Project Cost:	
o. South receipts	56. Min. Lateral Underclearance - Left:		Sufficiency Rating (Unofficial)	72.
CONDITION				
CONDITION / MATERIAL				RATING
58. Deck: SATISFACTORY-HAIRLINE CRACKS	, SPALLS, DELAMINATIONS. HEAVY EFFLORE	SCENCE FULL LENG	TH ALL SPANS Material: CONCRETE	6
58.01. Wearing Surface: GOOD- NEW BITUMINOUS PAVEMENT				
59. Superstructure:SATISFACTORY-SPALLS, CRACKIN	G, HEAVY EFFLORESCENCE			6
Paint				
60. Substructure: FAIR-BOTTOM OF SOUTH BENT CA	P EXPOSED W/ 1 PILE VISIBLE Material: CONC	RETE PIERS/END BEI	NTS	5
61. Channel: HEAVY BANK EROSION, FLOW DIRE	ECTED AT NORTH BENT DUE TO MEANDERING	G CHANNEL Material:	NATURAL/RIPRAP	4
62. Culvert:				N
<u>APPRAISAL</u>				RATINO
67. Structural:				
68. Geometry:				
69. Underclearance:				
<u>DEFICIENCES</u>				RATING
71. Waterway Adequacy: APPEARS ADEQUATE				8
72. Roadway Alignment: TRANSVERSE CRACKING. SOIL BU				
113. Scour Rating STABLE-ACTION REQUIRED. SEE E				

EXECUTIVE SUMMARY

HEAVY EFFLORESCENCE ALONG WEST DECKCOLD JOINT, FULLLENGTH, BELIEVED TO BE DUE TO BLOCKED DECK DRAINS AND SEDIMENT BUILD UP TRAPPING DRAINAGE. APPROACH SHOULDERS BUILT UP WITH SOIL DIRECTING DRAINAGE ONTO BRIDGE. END BENTS UNDERCUT. LIGHT EROSION AROUND PIERS. RECOMMEND INSTALLING STANDARD BRIDGE AND APPROACH RAILING AND MISSING BRIDGE END MARKER (SW). PRIORITY SHOULD BE GIVEN TO CLEANING DECK GUTTERS AND DRAINS TO ALLOW DRAINAGE. APPROACH SHOULDER BUILD UP SHOULD BE CLEARED AND DRAINAGE TURNOUTS SHOULD BE CONSTRUCTED AT SOUTH CORNERS TO DIRECT ROADWAY DRAINAGE AWAY FROM BRIDGE. FULL WIDTH PAVEMENT ON DECK WOULD ENCOURAGE DRAINAGE. UNDERPIN END BENTS INSTALL RIPRAP AROUND PIERS AND UP BENT SLOPES PARTICULARLY NORTHEAST CORNER.



East Approach Looking West




Looking at East Face Pier 2



South Face Looking Upstream



Looking at Drift and Debris at Upstream Nose Pier 2 (2)



ASSET NAME: 54-00197

IDENTIFICATI	ION	AGE OF SERVICE		LOAD RATING AND	POSTING
	185 - Indiana	27. Year Built:	1988	31. Design Load:	
	01 - Crawfordsville	106. Reconstructed:		64. Operating Rating:	
		42. Type of Service:	-	66. Inventory Rating:	
•	00000 - N/A	A. On Bridge	1 - Highway	66B. Inventory Rating (H):	
	BIG RACCOON CREEK	B. Under Bridge	,	70. Bridge Posting: 5 - Equa	
	CR 1200S	28. Lanes	•	41. Open, Posted, or Closed:	=
*	5400199	A. On Bridge:	2	66C. Tons Posted:	•
	00.10 E of CR 240 E	B. Under Bridge:		66D. Date Posted/Closed:	
		29. ADT:			
	86.85960 Decimal Degrees	30. ADT Year:		<u>INSPECTIONS</u>	
· ·	•	109. ADTT:		90. Inspection Date:	
STRUCTURE 1			-	91. Des. Inspection Frequency	24 Months
43. Structure Type – Main:		GEOMETRIC DATA		92. Critical Feature Inspected:	
	. 6 - Prestressed concrete continuous	48. Maximum Span Length		A N Mos. B N I	Mos. C:N Mos.
	06 - Box Beams - Spread	49. Total Structure Length:		93. Critical Feature Inspection Date:	
44. Structure Type – Appro	roach:	50A. Sidewalk/Curb Left:		A: B:	C:
	0 - Other	50B. Sidewalk/Curb Right:		PROPOSED IMPRO	VEMENTS
<i>31</i> 0	00 - Other	51. Bridge Roadway Width: (Curb-Curb):		97. Year Needed:	
·	3	52. Deck Width (o-o):		75A. Type Work:	
46. No. of Spans – Approa	ach: 0000	32. Approach Roadway Width:	22.0 Ft.	767 t 13pc 1767k	
107. Deck Type:	1 - Concrete Cast-in-Place	34. Skew:	15 Degree(s)	76. Improvement Length:	0 0 Ft
108. Wearing Surface / Pro	rotection System	47. Total Horizontal Clearance	24.0 Ft.	94. Bridge Improvement Cost	
A. Wearing Surface	1 - Monolithic Concrete	53. Vertical Clearance over Deck:	99.99 Ft.	95. Roadway Improvement Cost	
B. Deck Membrane	0 - None	54. Min. Vertical Underclearance:	0.00 Ft.	96. Total Project Cost:	
C. Deck Protection	1 - Epoxy Coated Reinforcing	55. Min. Lateral Underclearance - Right:	0.0 Ft.	Sufficiency Rating (Unofficial)	
		56. Min. Lateral Underclearance - Left:	0.0 Ft.	Sumciency Rating (Unumbia)	77.0
CONDITION					
	CONDITION / MATERIAL				RATING
58. Deck:	GOOD-MINOR HAIRLINE TRANSVER	SE CRACKS Material: CONCRETE			7
58.01. Wearing Surface: GOOD-POPOUTS, SAND COVERING DECK DRAINS Material: CONCRETE (8")					7
59. Superstructure:					
60. Substructure:	GOOD-LOCAL SCOUR AT PIERS, DE	BRIS PILE AT NOSE OF WEST PIER, MINOR H	IAIRLINE VERTICAL B	ENT CRACKS Material: CONCRETE PIER	S & END BENTS7
61. Channel:	FAIR-BRIDGE OVERTOPPED REGUL	ARLY Material: NATURAL/RIPRAP			5
APPRAISAL					
AITIKAISAL					RATING
67. Structural:					7
68. Geometry:					6
69. Underclearance:					N
	<u>DEFICIENCES</u>				RATING
71. Waterway Adequacy: .					5
, ,	SATISFACTORY- GRAVEL/SAND ON APPROACHES Material: RCBA/BITUMINOUS (72): SATISFACTORY-INTERSECTION WEST, CREST VERT. CURVE, STRAIGHT 6				
113 Scour Pating	STARLE WITHIN LIMITS		. ,		nits of footing or niles

EXECUTIVE SUMMARY

STRUCTURE PERFORMING WELL. LONGITUDINAL CRACKS FULL LENGTH OF WEARING SURFACE. MINOR TRANSVERSE CRACKS IN DECK. MINOR SCOUR AROUND PIERS. CHANNEL DEBRIS ACCUMULATED AT WEST PIER NOSE.RECOMMEND ADDING RIPRAP AROUND PIERS AND ALONG EAST BENT SLOPE, REMOVING CHANNEL DEBRIS, CLEANING GUTTERS AND DRAINS, AND INSTALLING BRIDGE END MARKERS. (2022)-LONGITUDINAL CRACKS FULL LENGTH OF WEARING SURFACE. MINOR TRANSVERSE CRACKS IN DECK. MINOR SCOUR AROUND PIERS. CHANNEL DEBRIS ACCUMULATED AT PIER 2 UPSTREAM NOSE.RECOMMEND ADDING RIPRAP AROUND PIERS AND ALONG EAST BENT SLOPE, REMOVING CHANNEL DEBRIS, CLEANING GUTTERS AND DRAINS, AND INSTALLING BRIDGE END MARKERS.